


software age

MAY 1968

**SOFTWARE MANAGEMENT THROUGH
SPECIFICATION CONTROL. SEE PAGE 8**

C315 20370&ST SDEPT 0 *
ST ANAL &SER BR B23 *
BUREAU OF NAVAL PERS *
DEPT OF THE NAVY *
WASHINGTON DC 20370 *

THE MAGAZINE FOR PROGRAMMERS • MATHEMATICIANS • ANALYSTS • EDP MANAGERS



Program yourself for progress.

Flexibility, diversity, challenge . . . are three vital ingredients for progress you'll find in abundance at AC Electronics. Why? Because, here at AC, you'll have a crack at a variety of jobs on some of today's most exciting and advanced projects. What's more, you'll be in on the ground floor of rapidly expanding computer activity. Example: a Hybrid Simulation System for future space flights already in the works. If you have a degree, plus two or more years' experience, look over the career opportunities listed below. Then write, phone or wire: Mr. R. W. Schroeder, Dir. of Professional and Scientific Employment, Box 507, AC Electronics Div., Milwaukee, Wisconsin 53201.

Real Time Programmers —

Perform system programming for special-purpose digital and hybrid airborne computers to achieve optimum system performance. Participate in check-out and engineering analysis of programs.

Simulations Programmers —

Design programs to perform math simulations and modeling of systems and vehicles. Pre-mission check of validity of systems and program accuracy performed on large-scale digital and hybrid computers.

Design and Programming Aids —

Develop highly automated systems for designing, fabricating, and programming small special-purpose computers, including the development

of programs and techniques to code, assemble, simulate and analyze operational programs.

Scientific Programmers —

Analyze and prepare computer programs for solution of engineering and scientific problems utilizing the I.B.M. system 360. Applications include missile trajectory simulation, flight test data reduction, design automation and automatic check-out systems for airborne computer software.

AC ELECTRONICS



MASTER NAVIGATORS THROUGH TIME AND SPACE. MARK OF EXCELLENCE.

An Equal Opportunity Employer

... or Improve it. That's what you'll be expected to do at Honeywell's EDP Technology Center. We're responsible for planning, designing and developing computer systems. To perform these responsibilities we need highly motivated programmers and analysts with a desire to prove and improve their state-of-the-art. To prove the importance which we attach to this task, you will find over 20 computers in our Technology Center — computers whose only function is to be at your disposal. Are you ready to improve your career potential?

PROGRAMMER/ANALYSTS

To be engaged in researching, designing and developing software packages which will maximize the efficiency of present and future generations of hardware. To demonstrate the imagination and

creativity necessary to the original conception and development of complex software systems. Openings exist at the intermediate (2 years experience) through senior levels. We are specifically interested in:

PRIMARY SYSTEMS DEVELOPMENT:

The design of complete operating systems to act as interface between customer applications and computer systems in a real time environment.

COMMUNICATIONS SOFTWARE:

To monitor, control and interface communications networks and computer systems in a real time environment.

MASS STORAGE:

The design of software to control and utilize random access storage devices.

COMPILER TECHNIQUES:

Translation and simulation of existing programs and systems so that they may be more effectively used with new hardware and software.

SCIENTIFIC SOFTWARE PACKAGES:

Development of software for use in operations research, linear programming, numerical control, math modeling and simulation.

Please forward your resume to Mr. David McGowan.


HONEYWELL

200 Smith Street, Dept. SA-5, Waltham, Massachusetts 02154

Opportunities exist in other Honeywell Divisions
Send resumes to F. E. Laing, Honeywell,
Minneapolis, Minnesota 55408. An Equal
Opportunity Employer.

The Other Computer Company:
Honeywell

PROVE IT



COMPUTER SCIENCE SERVICES LTV AEROSPACE

Would you like an opportunity to join a *NEW* computer organization (part of a large, established corporation) with a planned growth of 100 percent in the next 12 months, in *NEW* facilities and using *NEW* equipment such as IBM 360-65? The chance may be yours if you have the required background for one of the following positions:

BUSINESS APPLICATIONS

(Requires degree and two or more years experience.)

- **BUSINESS PROGRAMMING** — Program efficient solutions to complex problems through judicious use of concepts, modern techniques and the latest computing software and hardware.
- **BUSINESS SYSTEMS PLANNING** — Analyze problems and use knowledge of business systems and modern computer equipment to design systems to fit both the particular need and requirements of a totally integrated systems concept.

SOFTWARE TECHNOLOGY—IBM 360 Computers
(Requires degree and two or more years experience.)

- **SOFTWARE SYSTEMS**—Extend, document and maintain programming language processors (including FORTRAN IV, COBOL, RPG, ALC and SORT/MERGE) and operating systems.
- **LIBRARY ROUTINES** — Develop library subroutines to support scientific applications and plotting equipment (SC-4020 and CalComp.).
- **ANALYSIS PROJECTS** — Analyze requirements and develop plans for new hardware, software and applications.
- **STANDARDS & DOCUMENTATION** — Develop programming and operating reference manuals and compile program write-up file.
- **ASSISTANCE TO ENGINEERS**—Provide expert guidance for open-shop programmers to develop engineering applications.
- **DATA PROCESSING INSTRUCTOR** — Responsible for all application programmer, management and user training.

SCIENTIFIC APPLICATIONS

(Requires degree and two or more years experience.)

- **SCIENTIFIC PROGRAMMING** — Analyze and program a wide variety of scientific problems for the IBM 7090, 360 and other computers. Areas of current efforts including engineering design, real time and display generation, APT, scientific management techniques, simulations, large simulation projects, design automation using graphics, etc. Programming languages include FORTRAN, ALC and other assembly languages.
- **REAL TIME COMPUTING** — Requires BSEE and two or more years experience. Digital logic design, digital hardware and interface experience.

SEND RESUME TO Professional Placement
P. O. Box 5907 • Dallas, Texas 75222

**LTV AEROSPACE
CORPORATION**

A SUBSIDIARY OF LING-TEMCO-VOUGHT, INC.

an equal opportunity employer

software age

MAY, 1968

Vol. 2—No. 4

Copyright 1968, PRESS-TECH, Inc.

CONTENTS

PAGE

New Installations	6
Software Management Through Specification Control	8
Management's Prescription for "Computeritis"	16
Data Reduction Through Sampling in Computer Systems	21
Program Documentation: The Valuable Burden	24
Trouble-Tran Adventures for Fun and Profit	31
The Software of the Century ...	35
New Products	40
Confidential Inquiry Form	45
Index to Advertisers	46

Publisher	H. L. Rothra
Associate Publisher	David W. French
Advertising Manager	Norman Jacobs
Advertising Assistant	Betsy Pavkovich
Production Manager	William J. Murphy
Director of Circulation	Howard Rogers
Circulation Manager	Judith Arnopolin

Circulation of this issue more than 91,000

SOFTWARE AGE is published monthly
by PRESS-TECH, Inc.
(312) 869-1244

1020 Church Street, Evanston, Illinois 60201. Subscription free to qualified readers. Others, \$10/yr. Individual copies, \$1. Foreign subscriptions, \$10/yr.

Main Sales Office: Norman Jacobs (Adv. Mgr.) or Norman Brodsky, 1020 Church Street, Evanston, Illinois 60201—Telephone (312) 869-1244. Gerald Green, 60 E. 42nd, New York, N. Y.—Telephone (212) 697-5356. Richard Faust, 9800 S. Sepulveda Blvd., Los Angeles, California 90045—Telephone (213) 776-0100. David S. Wood, P. O. Box 189, Canton, Massachusetts 02021—Telephone (617) 542-1466. Richard D. Clemmer, 4900 Red Fox Drive, Annandale, Virginia 22003 (Washington, D. C.)—Telephone (202) 461-9792. Richard Faust, Palo Alto, California—Telephone (415) 327-8340.

CONTROLLED CIRCULATION POSTAGE PAID
AT MADISON, WISCONSIN

Work with advanced techniques at new Boeing fabrication facility.

The Boeing Company's newly activated Central Fabrication facility near Seattle, a modern complex of specialized fabrication and processing shops and equipment, offers exceptional ground-floor career opportunities to manufacturing systems and process engineers.

The company is extensively exploring highly advanced, integrated manufacturing operations concepts involving (1) computerized control of manufacturing processes and (2) integrated planning and control systems.

Boeing has initially invested \$120 million in this new facility. A large portion of this investment is in new



World's largest numerically controlled vertical boring machine is one of many modern pieces of equipment at Boeing's Central Fabrication facility.

machine tools, many with numerical control capability. The entire complex comprises 1.6 million square feet of covered area and includes four major factory buildings: an airplane wing spar and skin mill facility, a heavy machining facility, a tool fabrication facility, and a manufacturing process facility for metal bonding, plastic and fiberglass duct work.



Boeing 747 superjet is typical of advanced jetliner programs supported by new fabrication facility near Seattle. The 747 is scheduled for rollout this year.

The Central Fabrication facility supports all Boeing programs in the Seattle area. These include current, advanced jetliner programs such as the 747 superjet, the short-range 737 twinjet, and the U.S. supersonic transport, as well as a number of in-production and developmental space and missile programs.

Immediate openings exist for engineers at many levels of experience and responsibility in the following functional areas:

MANUFACTURING SYSTEMS ENGINEERING

Production Automation Systems —

Process control and operations, numerical control machine operations, computer-aided tool design, monitor and display systems.

Production Logistics Systems —

Planning and scheduling, tool and production control.

Management Information Systems —

Resource planning and control, simulation and model development, management reports and communications, cost schedule and technical performance.

MANUFACTURING PROCESS ENGINEERING

Flow Processes — Metal bonding, plastics and fiberglass, material handling.

Machining Processes — Mechanical and electronic controls, metal removal, forming and finishing, production automation.

Control Processes — Communications, computer applications, display and recording equipment, controls, models and simulators.

Qualifications: (1) three years related experience, (2) B.S. in engineering, mathematics, or the physical sciences, (3) Master's degree in business administration, or M.S. in engineering or mathematics.

You'll enjoy living in the Seattle-Puget Sound region where you can take advantage of year-round Western outdoor activity in the heart of the Pacific Northwest. From sea level to ski level is less than an hour's drive. The 172 San Juan Islands of Puget Sound are only two hours away. Enjoy sailing, fishing, hunting, golfing, clam-digging, beach-combing or mountain climbing at your pleasure.

Fill in and mail the coupon today. A Boeing representative will get in touch with you.

BOEING
COMMERCIAL AIRPLANE DIVISION

Please contact me with details about a career at Boeing's new Central Fabrication facility.

Name _____

Address _____

Phone (incl. area code) _____

City _____

State _____ Zip _____


I'm usually home between _____ and _____

_____ (hrs.) on _____ (days)


Degree/Specialty _____

Mail to: Mr. William Denman, The Boeing Company, Commercial Airplane Division, P.O. Box 707-BBB, Renton, Washington 98055.

EDIT PERFORATED TAPE . . .



*It's a splicer, it's
a gauge, it's a punch
The Model DL-141*



free samples . . .


1" perforated-tape splicing patches
. . . self adhering.

Mylar® or paper material. Opaque or transparent. Code and/or feed holes punched. 0.0025" or 0.0045" thickness. Costs as little as \$17 per 1000 patches. 1-foot splicing and correction tapes too!

Data-link makes a line of Splicer-Gauge-Punch combination units for perforated tape repairs and corrections, as well as electric tape winders and complete tape processing work stations.

free catalog

fully describes all
Data-link 8, 7 & 6, and
5 channel perforated
tape supplies and
equipment. Free sample
of assorted splicing
patches enclosed.
Write or use the
reader inquiry card
today!



Data-link Corporation

P.O. AP, 4546 El Camino Real
Los Altos, California 94022

For more information, circle No. 8
on the Reader Service Card

new installations

Systems Engineering Laboratories, Inc., Fort Lauderdale has ordered magnetic core memory stacks, valued at more than \$750,000, from Ampex Corp. Ranging in size from 100,000 to 200,000 bits, they will be used in various data processing systems.

Project Genie, University of California, Berkeley, has ordered from Scientific Control Corporation a 6700 Central Processing Unit. Project Genie, under the sponsorship of the Advanced Research Projects Agency, Department of Defense, does much work in the field of time-sharing computer systems. The new system at Berkeley will consist of the SCC 6700 Central Processing Unit and memory produced by other suppliers.

American Optical, major supplier of optical systems for U. S. space and defense programs, installed the new IBM 1130 computer to assist engineers in designing complex lenses and other optical systems that can photograph the earth's surface from speeding aircraft or probe millions of miles into space. Programmed into the computer is the desired operating characteristics of a proposed new system and received back is the most efficient configuration.

St. Regis Paper Co. has installed a high-speed data transmission system by Digitronics Corp. The system links the company's EDP Center in New York City with remote sales and manufacturing locations.

Allied Van Lines, Inc., long distance movers, has ordered Communitytype Corp. data communication equipment for proposed coast-to-coast management information network. The system is said to receive digital data at a speed of 1,000 words per minute. Compatible with most standard computers, it incorpo-

rates an IBM Selectric typewriter used for input and print-out operations.

American Collectors Association, Inc., an international trade association comprised of more than 25,000 independent agencies, and **Tri-Data, Inc.**, a computer consulting firm and service bureau, have installed GE-405 computer systems.

The GE-405 is the smallest member of General Electric's medium-scale GE-400 series of information systems. It includes a central processor with 8,000 words of memory, five magnetic tape units, a card reader, and a printer.

Dial-Data, Inc., Newton, Mass., has ordered a scientific data systems time sharing computer valued at \$1.1 million. The computer will be installed in the Washington, D. C. area to serve the entire metropolitan district and provide peak load and backup capability for the SDS 940 computer which has been in operation since 1967 in Massachusetts. Both the SDS 940 centers offer conversational interactive computer access to as many as 32 simultaneous users located at remote terminals installed in their own offices. The users connect the computer via regular telephone lines using teletype keyboard terminals.

The U. S. Bureau of the Census, which installed the world's first data processing computer, has increased its computing capabilities with a new UNIVAC 1108 System. The 1108 is being used by the Bureau for statistical processing.

Davis Brothers, Inc., the nation's fourth-largest wholesale drug distributor, has ordered a three-station computer network from Honeywell EDP. The company will keep inventory records on 30,000 items for customers using a Honeywell-developed software system called PROFIT.

If you're interested in working five years ahead of the times, learn about IBM's Federal Systems Division.

We're working at state-of-the-art levels—and we need programmers and analysts now.

Our Federal Systems Division is involved in a series of real-time projects for the Government that are about as advanced as anything in the field of computer technology today: trajectory analysis, orbit prediction, multi-programming, multiple-access concepts, acoustic instrumentation. And most of this work is being done using the latest computers and peripheral equipment available.

Our positions are located in Northern New Jersey and the Washington, D.C., area.

At IBM you'll find completely company-paid benefits that include life, medical and hospitalization insurance. IBM also offers you an exceptional educational assistance program.

Are you one of these people?

We need programmers and analysts with experience in one of two basic areas: information-handling systems and scientific-engineering programming.

Ideally, you should have a Bachelor's degree in Mathematics, Physics, Engineering, Economics, or Statistics. (Equivalent experience in some instances is acceptable.) You should have at least one year's experience.


Contact IBM today.


If you're interested in one of the hottest careers going in computer technology, we want to talk to you. Send a brief resume to: Mr. J.F. Ryan, IBM Corporation, Dept. BE1024, 18100 Frederick Pike, Gaithersburg, Maryland 20760.

It could be the most important resume you've ever written.

IBM®

An Equal Opportunity Employer





SOFTWARE MANAGEMENT THROUGH SPECIFICATION CONTROL

By F. Liguori

Sen. Proj. Member, Technical Staff
RCA, Burlington, Massachusetts

About the Author

Mr. Liguori received his BSEE degree from Tufts University in 1957 and an MBA from Hofstra College in 1960. He received his formal computer education at the graduate school of Adelphi College. Since joining RCA in 1962, he has been involved in test designing and programming for various general-purpose automatic test systems, including the Multipurpose Test Equipment (MTE) and the Land Combat Support System (LCSS) for the U. S. Army Missile Command and the Depot-Installed Maintenance Automatic Test Equipment (DIMATE) for the U. S. Army Electronics Command, and a newly installed commercial automatic test system. For the past three years he has been a principle contributor to Independent Research and Development studies on advanced programming techniques for the RCA Automatic Test Equipment product line.

Contrasting software with hardware is a convenient way of describing software to non-programmers. This emphasis on differences has led to a common misconception in industry that the two products are inherently different and thus, their development must be handled differently. Close analysis of both tasks reveals often overlooked similarities. In fact, the two products are so similar in content that the commonly used formal techniques for managing hardware developments apply equally well to software development.

This article offers the rationale behind the thesis that hardware and software development tasks are in fact quite similar. It then discusses the applicability of specification control to software development, emphasizing how each advantage of specification control applies equally well or more so to software development tasks.

The conclusion is that software management is not inherently different from hardware management. The same tools of control may be (and in fact have been) successfully used for software development tasks. It is, therefore appropriate, and necessary for project managers to provide more definitive direction of software development tasks through detailed specifications without requiring personal proficiency in software design.

■ Examination of documents commonly used in industry to control system design and engineering reveals a lack of understanding of the nature of software and methods of software development control. This is particularly evident in Requests for Quotations (RFQ's) involving computerized systems requiring both hardware and software development. Typically, such RFQ's consist of 50 pages or more of very detailed technical requirements. They include not only the necessary performance characteristics, but often even dictate the basic method of implementation of the system to be designed. Of these 50 or more pages, often as few as two or three pages and certainly less than ten percent of the document is devoted to software specification. Yet, software for the system may cost as much or more than the hardware. This over emphasis on hardware is indicative of an unique pre-occupation with hardware characteristics and a lack of understanding of software techniques and requirements. Software characteristics, which by and large dictate operational characteristics of the completed system, are left vague and undefined.

Work statements and design specifications, which are outgrowths of the RFQ, further reflect the vagueness with which software is controlled. The result is that, unless the contractor selected happens to be unusually competent in software development, this aspect of the system is left to be worked out during the hardware development phase when it is impractical to make the optimum hardware/software configuration tradeoffs.

The Automatic Test Equipment product line at RCA has traditionally involved a complex interplay of hardware and software. Experience has proven the value of detailed software work statements and design specifications. This paper develops the rationale behind the similarity between hardware and software development and management tasks and discusses the advantages realized by close control of software tasks through definitive specifications.

Similarity of Software and Hardware Systems

Hardware and software are often contrasted to explain the special problems of software with respect to the familiar base of hardware development. And, indeed there are many aspects of software development that make it different from hardware. Hardware is developed in discrete stages (paper design, breadboard, engineering prototype, etc.) that progressively constrain system changes. Software stage boundaries do not seem to progressively constrain software system changes. The obvious reason is that software appears inherently more flexible (therefore changeable) because it is structured with "paper" rather than fabricated hardware. Ironically, it is this "advantage" of software that is really its nemesis. Nothing can hamper final designs more than susceptibility to change, and nothing is more fatal to schedules than design changes.

OPERATIONS RESEARCHERS SYSTEMS ANALYSTS PROGRAMMERS

Experienced

You (and your children) can grow in what U.S. News & World Report calls one of "The Pleasant Places to Live in the U.S." Neenah is one of a dozen live-wire communities in the Fox Cities complex reaching from Green Bay to Oshkosh that includes 250,000 people. Busy with work, play and civic improvements in an invigorating climate, the people enjoy living in progressive communities. You will appreciate being less than ten minutes from work (and from the golf courses). Your wife will appreciate being less than ten minutes from schools, shopping centers, churches, the doctor and the swimming pools. You'll all enjoy the lakes, parks, snowmobiling, boating, skiing and fishing.



Here in Neenah, Kimberly-Clark, one of the world's foremost paper products manufacturers, offers opportunities in our expanding Information Services Center. Here we are developing information packages and data processing networks using IBM 360 computers.

We need people with a minimum of two years of experience in the positions named for the following openings.

OPERATIONS RESEARCHERS

Bachelors degree with heavy math emphasis or equivalent experience. Technical working knowledge of O/R techniques, particularly simulation, probability and statistics. Concrete experience with successful **application** of these techniques to business problems. Advanced degree of added value.

SYSTEMS ANALYSTS

Bachelors degree in Business, Mathematics or Engineering degree would have included business courses. Advanced degree of added value.

PROGRAMMERS

Degree preferred or equivalent business experience. 360 BAL, 360 Cobol, 360 PL/I preferred. Medium scale tape/disc acceptable.

RELOCATION EXPENSES PAID

Contact us (collect) at (414) 722-3311, Ext. 2653, or better still, send resume with past experience to C. L. O'Meara, Manager, Corporate Recruiting.




Kimberly-Clark Corporation

North Lake Street
Neenah, Wisconsin 54956

An Equal Opportunity Employer

PORTABLE
Roto-Angle®
REPLACES
4 SEPARATE
DRAFTING TOOLS



A four-in-one drafting instrument that permits engineers and students to solve problems faster, with drafting-machine accuracy. The Roto-Angle replaces the standard triangles, the protractor, and the adjustable triangle because it performs all the functions of these tools and does them faster and with greater accuracy.

Use with only a board and T-square. The ruling arms, which are channeled for clean inking, are made of one piece which is pivoted so it can be swung either right or left through 90°. The protractor has a scale of 90° and is also pivoted and can be swung in either direction. The ruling arms and protractor can be moved independently of each other and can be locked together (and to the base) in any position.

With sturdy carrying pouch

Only \$750

Postpaid

SCIENCE/SYSTEMS

P. O. Box 1176
 Evanston, Ill. 60204

SA-5

Please send me at the address below:

THE PORTABLE Roto-Angle®

(name)

(address)

(city)

(state)

(zip code)

A second characteristic of software that makes it more elusive to schedules is its camouflaged nature. Unlike hardware developments which go through visible stages of development, preliminary software and debugged software are of the same general appearance. Even when it is apparent that a task is still in the process of completion, it is much more difficult to determine percentage of completion of software as compared to hardware developments in progress.

Despite the obvious differences in hardware and software it is the thesis of this paper that software and hardware systems have greater kinship than disparity. Furthermore, mismanagement of software systems development stems from overemphasis of differences and failure to recognize and capitalize on similarity. Once this thesis is accepted, it follows that the methods of hardware systems development can be successfully applied to software systems development. This causes two seemingly divergent disciplines to converge in most system applications. Hence, it allows well developed techniques to be applied in a field much less understood by management people¹ who control the integrated system development at the critical point—where software and hardware have a common manager.

The Basis of Similarity

To see the commonality between software systems and hardware systems one must examine not the form of the finished product but rather the resources required to develop each system. In either development, basic resources are time, manpower, and materials, all of which have a common denominator in dollars. These resources are common to all human endeavor so it is necessary to further investigate the types and quantities involved as well as their interrelationships to prove or disprove substantial correspondence between hardware and software development tasks.

When dealing with a system under development, whether it be hardware, software or a combination, schedules typically involve a year or more. Usually, there is no substantial difference in period of performance for hardware and software system development when comparing tasks of approximately equal dollar volume.

In any system development, manpower (particularly engineering labor) is by far largest single cost. Cost analyses of past research and development contracts show that manpower typically accounts for 75 percent of total cost. Variations are geared to the ratio between purchased and fabricated items in the system. Where all subsystems are specially developed, the labor approaches 90 percent of the task, whereas systems configured largely from off-the-shelf units yield much lower labor percentages. If one could determine the percentage of purchased item costs, these items too would be seen to be largely labor burdened except where very high production rates exist. In software develop-

ment, also, labor generally runs 75 percent and it can run as high as 90 percent of the task. Even in control system programming where certain adaptor hardware elements are attributed to "software" costs, about 80 percent of the cost is expended in labor, largely engineering.

From this it is apparent that, in either hardware or software systems development, engineering (or other professional) labor comprises the bulk of the cost. Furthermore, the differences between software and hardware system development labor rates are negligible. The professional engineer or scientist plays the major role in both.

Material costs are naturally higher for hardware system development, being in the order of 25 percent, as compared to about 5 to 10 percent for software materials. In software efforts, however, there are generally equipment rental costs involved to debug programs on a computer. These typically are 10-15 percent of total costs. Rentals are often treated as "material" costs, at least in purchasing procedures. With rentals so classified, the ratio of materials to total costs also becomes quite comparable for hardware and software systems.

In conclusion, all factors of production are close to equal for either hardware or software developments involving equal dollar volume. It is also apparent that the largest single cost by far is professional labor. Hence, the most precious ingredient of any system is the "intelligence" expended in its design and construction. Since any effort can be reduced to management of factors of production, management of software and hardware development tasks can be handled essentially in the same manner.

Method of Control

The instruments of control in any system development are managers and procedures. The managers of hardware systems and software systems are almost always technically or scientifically disciplined professionals, at least at the project management level. Salary levels and prestige are approximately the same for projects of equal dollar volume since they each involve approximately the same number of personnel in the same salary ranges. Hence, the only variable between hardware and software management is the set of procedures.

The procedures for hardware management are by far more standardized and apparently more effective than for software.² In fact, there appears to be no standard approach to large scale software developments. Although most software managers have learned to rely heavily on documentation for control, the manner of task specification, quality control, product standardization and change control is quite loose in many organizations. With an absence of formal procedures, success or failure in software tasks depends much more heavily on close personal supervision and the quality of such supervision.



MASSACHUSETTS INSTITUTE OF TECHNOLOGY INSTRUMENTATION LABORATORY

PIONEERING IN SYSTEMS PROGRAMMING

The laboratory needs self-starting individuals who want to be responsible for a project from its inception, through design, implementation, testing and documentation. A unique atmosphere is provided for such professionals because of the broad scope of its involvement in the computing field. The range covers maintenance and modification of our OS/360 system, running on two IBM 360/75's, to the design and development of computers and computing techniques for the next generation of spaceborne guidance systems.

Staff assignments exist at all levels for programming professionals with solid experience in the design and implementation of large scale computational systems. This includes monitors, remote job entry and conversational programming, list-processing languages, algebraic compilers and assemblers in addition to operating systems.

Interested candidates should forward their resume to Mr. John J. McCarthy, Professional Staffing, 68 Albany Street, Cambridge, Massachusetts 02139, or call (617) UN 4-6900, Ext. 5378. M.I.T. is an equal opportunity employer.






Figure 1. Documentary Control of the Engineering Design Process

While supervisory talent is a required commodity in any endeavor, heavy dependence on such a rare commodity is risky. It is not without justification that American Industry places as little dependence on personalities as possible, preferring to rely heavily on policy and procedure manuals. Software management should follow this example and shift some of the control from personal management to procedural management.

Management Control Tools

PERT and similar management control procedures are commonly used today. Many of the larger concerns are utilizing computers to implement these control procedures, thereby greatly facilitating correlation and dissemination of control data. Software as well as hardware elements of a system are included as milestones in the overall schedules. This has allowed broad control of tasks but the guidance for meeting individual milestones must come from more detailed technical direction. In hardware development, the process is well defined by formal documentation. A typical development process under document control is shown in Figure 1.

This process is a familiar one and need not be explained in detail. Two points are worth noting, however.

- (1) Normal process flow is from customer requirement to end product with changes as a counter force. The more significant the change, the greater the impact and, hence, the further against the productive stream it flows.
- (2) The major point of contact between the management functions and the engineering effort is the work statement which references the design specification. The

specification, therefore, provides the major technical direction from objective to accomplishment.

Advantages of Specification Control Techniques

Borrowing from the hardware management discipline, the specification should be the basic control device in software development efforts. A brief review of advantages offered by specification control of hardware is worthwhile, for each advantage applies equally or more so in software management. A specification, when properly and timely executed, provides:

1. A clear, indisputable definition of the task requirements in terms of design objectives.
2. A legal base for negotiation.
3. A readily referenced source of guidance.
4. A logical means of subdividing tasks and interface handling.
5. A standard of measurement for progress review.
6. A standard of measurement for finished product performance.
7. A source of direction independent of personalities.
8. A means of standardization control.
9. A vehicle with which to build new designs based on past projects.
10. A means for maximum span of control by management.
11. A handy tool for orientation of personnel assigned to the project after formal orientation.
12. A basis of reference and control of inevitable changes.

The advantages listed for specification control over less formal, personal control of hard-



**If you're the kind
of systems
programmer who
has a mind that's
deep enough
for Kant,**



**broad enough for
science fiction,**



**and sufficiently
precise to enjoy
the esoteric
language of the
computer,**

look into RCA. You're our kind of man.

You probably think far ahead
of your time.

You want to take software out
of its infancy. Into the 4th, 5th
and 6th generations.

You want a chance to
influence hardware design,
instead of the other way around.

You want a variety of projects
with definite objectives, instead
of an endless task.

You want challenging work
and inspiring rewards.

If this is what you're looking
for, find it at RCA.

Write to us if you've had
experience in language
processors, operating
systems, utility systems or
communications systems.

We also have openings in
Sales, Field Systems Support,

and Product Planning and
Engineering.

Contact Mr. J. C. Riener,
Dept. SW-1, RCA Information
Systems Division, Bldg. 202-1,
Cherry Hill, New Jersey 08101.
We are an equal opportunity
employer.

RCA


OPENINGS

(Management Information Systems)

- Multi-Processing
- Multi-Programming
- On-Line Teleprocessing
- Large, Random Access Data-base Files
- Graphics
- Time Sharing
- Digital High Speed Data Transmission
- Advanced Data Collection Systems
- Advanced Data Reduction/Performance Analysis Systems
- Large-Scale Scientific/Business Applications and Management Information Systems

ROCKETDYNE

Division of North American Rockwell



At Xerox, we look at our programmers...



and see managers...

The kind of programmers we look for aren't satisfied with narrow EDP solutions. They look for ways to improve business operations with systems thinking in the broadest sense. Using creative analysis and synthesis to enhance customer service in every facet of our dynamic marketing environment. Which, by the way, is part of the reason all our programmers are called programmer analysts.

If you're getting the impression that programming at Xerox is more than being a man-machine interface, you're right. It's an exposure to almost every facet of our operations, through planned

rotation from system to system. Encompassing business modeling, market research and information, manufacturing/inventory/equipment control, general accounting and engineering research...plus some applications so unique we can't even mention them. We refer to it as our Talent Enhancement Program: multiple, simultaneous, short (3-6 month average duration) projects plus room for individual contribution equal a strong innovative staff for us and broad experience for you...which is the best preparation for better things to follow.

If you have a Bachelor's Degree

and/or experience with an IBM 360 or 7000 system, or a Univac 1108, using COBOL or AUTOCODER, there could be a future management opportunity waiting for you at Xerox. To find out more about the opportunities open at Xerox on all levels, send your resume, including salary history and requirements to Miss Marie Hartigan, Dept. MZ-69-E1, Xerox Corporation, P.O. Box 1995, Rochester, New York 14603. An Equal Opportunity Employer (m/f)

XEROX

MANAGEMENT'S PRESCRIPTION FOR 'COMPUTERITIS'



J. A. Salvail

Jack A. Salvail has been a career civil service employee with the Air Force and Navy for more than 20 years. He now serves as Special Assistant to the Technical Director of the Naval Command Systems Support Activity. He was project leader for *Management Data System, Planning Guide for Computer Program Development* and the *Selection of Technical Computer Personnel*, NAVCOSSACT projects.

■ Today the Computer Science and Management effort is plagued with a most serious illness. This illness is the inability to communicate. It has affected not only men working directly with the computer, but all men connected with the field of Computer Science and Management—technicians developing the system, salesmen, and those responsible for directing their activities and the overall business operations they effect.


This situation is encouraged by the variety of definitions individual computer technicians attribute to the functions of programming or analysis. Invariably, no two answers are identical, and in some instances a new title will be added to define the same function. For example, instruction is interchanged with coding as one function of programming. One never ceases to be amazed at this new, fast-growing vocabulary and its authors who have exceeded the time-worn medical profession in developing a language unto themselves.

Confusion within the computer profession has likewise contributed to confusion in dealing with outsiders. The lack of effective communication with users has been

particularly harmful in creating mistaken impressions of the abilities of the computer, and in hampering understanding between computer professionals and users during system development.

The conservative Government Bureau of Budget has issued an automatic data processing glossary to assist in organizing the confusion of definitions in Government. Private industry is also taking steps in this direction, but much is yet to be accomplished. Progress has also been made in the managing and monitoring of system development, so that users can be more aware of the procedures involved. The following practical management prescriptions, representing much of the recent progress, are recommended to assist management as well as technicians in the care and treatment of "computeritis".

Prescription #1 is a word to the wise that hasty decisions to "computerize" are always costly, usually disappointing, frequently embarrassing and sometimes disastrous. Experience indicates that some officials may have been unduly influenced into making premature decisions in this area. The feeling that you don't comprehend "why"; that you're either "obsolete" or "stupid"; that the "halo effect" surrounding the concept of computer system operations and the impression that possession of an ADP system is the status symbol of progressive management; and that "everybody's doing it" are all factors that influence the making of pre-



ture decisions. The decision to "computerize" some data operations in your organization is NOT an easy one, and it should not be made without careful, objective and systematic deliberation.

We cannot question the revolutionizing influence of computers on information handling today, nor their tremendous, almost unlimited potential. However, automated data

PLACE
5¢
STAMP
HERE

press tech inc.

software age

1020 CHURCH STREET

EVANSTON, ILLINOIS 60201

Gentlemen:

- ☐ I am not presently receiving a copy of **software age** addressed to me. Please enter my free subscription.
- ☐ Please send advertising rates. I have included my company affiliation, company address and title in box.

Name

Home Address

City State Zip Code

If you wish advertising rates, please fill out.

----- (-----) -----
Title AC Telephone

Company Name

Company Address

City State Zip Code

To receive **software age**, circle the most appropriate number and letter below to describe your present position and experience.

MY SPECIALTY:

- 1—Systems Analysis
- 2—Math/Math Analysis
- 3—Operations Research
- 4—Scientific Programmer
- 5—Business Programmer
- 6—EDP Management
- 7—EDP Instructor
- 8—EDP Consultant

9—-----
other, incl. EDP student,
operator, technician, etc.

PRIME EXPERIENCE IN:

- 1—Aerospace/Defense Industry
- 2—Non-Defense Industry
- 3—Commercial/Finance
- 4—Research Organization
- 5—Govt./Military
- 6—EDP Consulting
- 7—Transportation/Utilities
- 8—Education/Library

9—-----
other, specify

I WAS BORN:

- A—1920 or before
- B—1921-25
- C—1926-30
- D—1931-35
- E—1936-40
- F—1941-45
- G—1946-50
- H—1951-55

I HAVE:

- ☐ Technical Degree
- ☐ Non-Technical Degree
- ☐ No Degree

☐ Check here if you have analog or hybrid experience.



... in our

SCIENTIFIC & COMMERCIAL COMPUTER-BASED

ANALYSIS & DESIGN SYSTEMS

You can. You'll like what you see at Sikorsky Aircraft—a company dedicated to producing the most advanced VTOL airborne and surfaceborne transportation systems.

And you'll like working with a select group of stimulating, top-talent people . . . on abundant and provocative challenges. You would be applying your professional talents to specifying, designing and implementing advanced computer-based technical and commercial systems.

Our current equipment includes Univac 1108's and IBM 360's with Graphics and Teleprocessing.

Current and planned applications include—

Scientific: Man/Machine Interactive Graphics in Engineering Analysis and Design.

Development of Batch Programs and Systems in all engineering disciplines.

Commercial: Data Base and Real Time applications in Accounting, Manufacturing, Purchasing, Inventory Control and other related areas.

We have exceptional assignments at all levels of experience for:

COMPUTER SYSTEMS
PROGRAMMERS AND ANALYSTS
FOR BOTH COMMERCIAL
AND SCIENTIFIC FIELDS



Sikorsky Aircraft

U
A

DIVISION OF UNITED AIRCRAFT CORPORATION

STRATFORD, CONNECTICUT

An Equal Opportunity Employer

You and your family will find the unique cultural and recreational advantages of pleasant Connecticut to be abundantly satisfying. And our interest in your continuing professional development is exemplified by our corporation-financed Graduate Education Programs. They are available at these fully accredited schools: Bridgeport • Brooklyn Poly • CCNY • Columbia • Connecticut • NYU • Rensselaer (Hartford Grad. Center) • Stevens • Trinity • Yale.

Send your resume in confidence, stating salary requirements, to Mr. Leo J. Shalvoy, Professional Employment.



for
programmers
only:

The hard facts

about Software
—and you!

As you well know, in the computer field, Hardware and Software go together—like ham & eggs, red, white and blue, boys and girls, and other natural and essential combinations.

As you also know, a Software program can be no better than the Hardware that will handle it. Now—UNIVAC Hardware is acknowledged to be number one technologically in the computer business. And that is an important reason why our Software programming section is so attractive to talented people looking for the likeliest place to work and grow.

Right now, there are especially desirable opportunities available in real time applications, command and control, compiler and machine language development, and research and methods programming.

If you'd like more hard facts about what Univac has programmed for talented Software people, write: R. K. Patterson, Personnel Manager, Dept. 118.

UNIVAC
FEDERAL SYSTEMS DIVISION
2750 WEST SEVENTH BLVD.
ST. PAUL, MINNESOTA 55116
AN EQUAL OPPORTUNITY EMPLOYER M/F

processing is not a simple panacea for all data processing ailments.

- NOT ALL management problems are automatically banished by simply plugging in "black boxes".
- NOT ALL manual operations are necessarily slower, less efficient, and more expensive than ADP.
- NOT ALL organizations *need* ADP in order to accomplish their mission.
- NOT ALL data and record keeping operations are adaptable to ADP.
- NOT ALL organizations have enough ADP requirements to justify a computer system.
- NOT ALL organizations can *afford* ADP.

The whole process of effecting a computer application—from the initial decision to automate, through feasibility and application studies, equipment selection, systems design, programming, staff training, site preparation, conversion procedures, and testing to full ADP operation—usually requires several years, tens of thousands of man-hours, and hundreds of thousands (sometimes millions) of dollars in initial activating cost alone.

Most businesses of any consequence have several basic computer applications: payroll, fiscal accounting, personnel information, inventory, and taxes. Even with these, the purchase of a computer and, more important, the hiring of a staff to run and maintain the systems is very costly. Unless a business can utilize the computer at least 12 hours a day, the saving resulting from the installation is frequently disappointing.

Prescription #2 is that businesses with few applications or a questionable need of a computer installation should initially obtain the services of a Computer Service Bureau. During this introductory period, the firm can establish the data base, permit the members of the organization to become conversant with the method of obtaining and submitting computerized information, and review and evaluate the format, content, use, and frequency of output generated by the automated changeover.

After the foregoing period, if additional computer time and in-house system applications are clearly

evident, the purchase or rental of a computer should be seriously considered.

Should you succumb to "computeritis", the communication bit will continue to be a serious problem. How does Management make its needs known and control a function that speaks strictly in a foreign language and for which there is no standard measure of productivity? One has no dozen, no pound, no inch or gage of production progress.

Prescription #3 is designed to scratch the surface of a new plateau and prescribe the following uniform titles and definitions of phases and progress for the orderly development of a complete automated system. Each phase constitutes and defines an orderly, sequential step-by-step requirement in automating a manual procedure into a computerized operation or developing a so-called complete software package. If these milestones were adopted universally by businessmen and required of the computer industry, a positive bench mark and common basis of reference of work and progress would be applied across the field of Computer Science. Incidentally, the Government, the largest user of computers, has generally followed this phasing in developing an ADP system.

Development Phases

1. **System Analysis**—The process of evaluating and determining methods and procedures for currently doing the operation proposed for automation.
2. **System Design**—Designing, developing, and describing the methods and procedures to automate the operation from its present status.
3. **Program Development**—The flow charts, program designs, file arrangements.
4. **Coding**—The Computer instruction and desk checking.
5. **Check out**—Testing to assure the instructions are accomplishing the programs and planned output.
6. **Documentation**—A functional description of the system, (Users Manual), a Programmers manual, and a Computer Operators manual.
7. **Data Collection and Conversion**—Converting existing rec-

ords to acceptable automated data elements and establishing the data base.

8. **Assistance and Training**—Guidance, instructions, and re-orientation of personnel and procedures associated with installation, maintenance, and use of newly automated system.

The adoption of these phases and their definitions facilitate a better understanding of what is being done and what is expected in the orderly, progressive development of an automated system.

Presently, an average total software system of a single business operational phase may take 9 months to over a year to develop. Upon inquiry the system technician would now indicate to a management official that he is in "analysis" at various intervals over a 3 to 4 month period and subsequently in program development over the next 2 to 3 month period. This is very taxing to a manager's sense of humor and hardly helpful in defining progress, whereas the proposed phase description of progress or status of development would be acceptable and generally understandable to all concerned.

The phase system will also identify programming changes to existing systems or feasibility or similar system studies that may be initiated. Changes to an existing system are identifiable under the phases associated with programming as described in two documentation manuals (Programmer's manual and Operator's manual). A feasibility study is identified as the analysis phase and is documented by the management functional description. By applying the phase identification, both parties involved understand and identify what is expected and the relative degree of progress or delays. Accordingly, misunderstanding during development of an automated system is materially alleviated.

Prescription #4, and a must product of the analysis function at the conclusion of system analysis and system design phase, is the submittal of a "management's functional description" of the proposed system. This is one of the three publications in the documentation phase effort. It is essential that this document be written in a language understanda-



Space shots to the moon... golf shots to the green...

JOIN US IN BOTH AT THE J. F. KENNEDY SPACE CENTER IN SUNNY FLORIDA.

NASA's lunar module (LM), which took its first space journey in late January, was a talkative "bug." ITT Federal Electric Corporation's project team listened in and monitored each action and reaction of the craft from when it was first mated to its launch vehicle until the mission's end. The successful flight was a significant step toward the manned lunar landing.

As a prime contractor, Federal Electric Corporation has some 1500 professionals on the talented NASA/industry team involved with the Saturn Apollo program. Our fast expanding computation work at the Center provides real-time scientific test support, data reduction, systems analysis, computer operations and data storage and retrieval. This scientific, engineering and administrative support activity utilizes two GE 635 time sharing digital computer systems with 16 magnetic tape units, 128K word storage, a 786K word drum and real-time input/

output controllers on each system. We also use an IBM 7010 computer system for financial management and an IBM 1050 connected to a separate IBM 1440-7010 computer system for a real-time 30K item inventory system.

While the size and complexity of our mission provides you with talent-extending excitement, the great climate here in the heart of Florida's beautiful East Coast offers you unmatched relaxation. There's sun, sand and seashore plus water skiing, surfing, fishing, hunting and superb golf. It's comfortable living (at well below the national average cost), lots to do, and the perfect climate for doing it.

Please forward your resume, including salary history, in complete confidence to Mr. L. A. Hamilton, Federal Electric Corporation, Suite 501, Cape Royal Building, Cocoa Beach, Florida 32931.

FEDERAL ELECTRIC CORPORATION **ITT**

ITT's World-Wide Service Associate. A Plans for Progress Equal Opportunity Employer (m/f)

SUPERVISOR OF CORPORATE SOFTWARE

SUPERVISOR OF OPERATING SYSTEMS

We seek two individuals who have the creativity, enthusiasm, desire and ability to direct and motivate a group of systems analysts supporting an OS/360 large scale multi-computer complex.

We require in-depth experience with OS/360, FORTRAN, COBOL, Teleprocessing, Communications, and Direct Access Data Management. If you have a college degree and a minimum of two years successful industrial experience in these areas, the corporate level positions we offer will provide a direct challenge to your abilities and future progressive growth opportunities in management.

If you are action oriented and interested in fulfilling your inherent growth potential, send a detailed resume, including salary information in confidence to:

George J. Vogel
Manager, Corporate Computer
Center
Allis-Chalmers, Box 512
Milwaukee, Wisconsin 53201



ble by Management. This document is the functional description and work flow of the changes in input, output, and current procedures of operations necessary to automate or computerize the operation. It includes information concerning form design, implementing methods, and procedures as well as any organization and personnel changes.

Prescription #5 points out that it is essential for Management and technicians to agree entirely on the foregoing management automation plan described in the function description and that no or few minor changes be made in the procedure after agreement and commencement of the programming phase. Any changes should be resolved prior to commencement of programming. Repeated changes during programming are very costly, can delay the delivery schedule, and have been known to cause programmers to grow beards and wear torn sneakers. It is wiser to make changes after the system has been totally developed.


Prescription #6 and the last word to the wise, but one of the most important: the best engineered system in the world is only as good as its data base, a fact frequently overlooked by managers or deemphasized by operating officials. Therefore, initially, put your chief executive in charge of establishing your data base. This could prevent re-funding \$6000.00 to an already overdue customer to ordering 20,000 typewriter ribbons for your secretary. ■

MR. EMPLOYER

If you would like a SOFTWARE AGE media file including our advertising rate card, circulation information, etc. write or phone:

Norman Jacobs
Advertising Director
software age

1020 Church St.
Evanston, Ill. 60201
(312) 869-1244



WORLD FAMOUS CURTA

PORTABLE PRECISION CALCULATOR

- weighs only 8 oz.
- adds—subtracts—multiplies
- divides—squares—cubes
- extracts square roots
- accumulative multiplication
- multiplication or division by constant factor
- figures: percentages
- percentage increase or decrease
- compound percentages
- calculations—calculation of distance and azimuth—linear
- interpolation—solves formulae

comes in two models

	MODEL #1	MODEL #2
diameter	2-1/16"	2-9/16"
height	3-3/8"	3-5/8"
weight	8 oz.	12 oz.
digit cap.	8x6x11	11x8x15
PRICE	\$125.00	\$165.00

Furnished with shock proof container.

LEATHER CARRYING CASES (2 Styles Available)

Carries "Curta" in Container		
#S-1	SMALL	\$14.00
#S-2	LARGE	\$16.00

Carries "Curta" Only

#1	SMALL	\$10.95
#2	LARGE	\$11.95

MONEY BACK GUARANTEE


You may purchase either model on a money back basis. If you are not completely satisfied with the Curta Calculator, you may at any time within a 30 day period return it for your money back. In addition all calculators carry an unconditional guarantee against any defect in parts or workmanship.

To order specify Model # and case style and send check with your order to:

SCIENCE/SYSTEMS

P. O. Box 1176, Evanston, Ill. 60204

DATA REDUCTION THROUGH SAMPLING IN COMPUTER SYSTEMS



Donald V. Mathusz

Donald V. Mathusz, 37, is currently an Operations Research Analyst at the Annapolis Division of the Naval Ship Research Development Center, Annapolis, Md. He has directed or been a consultant on projects dealing with data systems design, simulations, statistics and reliability. He received a BIE degree from Syracuse University in 1960; the Masters in Management Engineering from Rensselaer Polytechnic Institute in 1963; and he is currently pursuing the Ph.D. at the University of Maryland.

INTRODUCTION

■ The populace in general is fascinated by the speed with which computers can digest data. Many systems people fall into the same pattern of thinking, and so—do not consider (seriously) techniques of data reduction. These techniques can reduce work at many levels, from the systems design stage through implementation problems, to actual alternative processing methods that could save substantial CPU time. In this paper, we will discuss sampling in a general fashion, as a data reducing technique.

Part of the orientation problem is that very little has been written about actual applications in the general business orientated data processing vernacular*. Mathematical statistics, upon which sampling de-

pends for its theory, is only now coming into vogue in our business schools. For this reason, few business orientated systems people presently have any mathematical statistics background. (The Engineering/Sciences areas are a bit better off, with one statistical course in the general undergraduate curriculum.)

The body of the available literature, however, tends to the graduate level. This is a bit high for reference to a first try at understanding and possible applications by the ordinary analyst. A bibliography of references is included for those staunch enough to advance into the area. This bibliography is not expected to be complete, but Tukey's article examines the current state-of-the-art under the broad heading of data reduction, while at the other extreme, Moroney's well-known little book is about as fine an introduction to the subject matter as can be had. The Grant and the Cyert & Davidson books are of a higher, intellectual level, (but still very reasonable), while the others get a bit more involved.

One can hardly escape the fact that I have not gotten into the actual techniques of sampling itself. Here, I would agree with most statis-

ticians that a little knowledge can be harmful. What I am attempting to do, is give the average systems analyst insight into when it might be very profitable to call in a consultant. Please note that you may well have people in-house who can be consultants, at least for situations that only call for simple random or possibly simple strata sampling. These people are often found in Statistical Quality Control, Reliability, Operations Research and Marketing Research . . . Hopefully, they should also know when to call in outside consultants.

All this is to point out the subject matter is admittedly involved, but not impossibly so, and certainly not to the point that its lack of general use would have us believe. Next we will take up the basic criteria of how we can recognize when we have a possible sampling application, or a tiger by the tail.

CRITERIA FOR DATA SAMPLING: AUDATA OR STODATA:

A first easy decision to make is, are we processing data which must be accounted for in the "balanced book" audit trail—accounting sense? If the answer is yes, we have audit type data or audata (acronym). On the other hand in many cases, (espe-

* A recent exception is Arkin, A., article in the *Journal of Accounting*, October, 1955, pp. 44-48.

UNIVAC world headquarters wants pro- grammers

who actually
like
programming

At UNIVAC world headquarters in suburban Philadelphia—Blue Bell, Pa., in fact—the emphasis is on people and ideas. We know that every bit of software springs from a human idea. And without it, the most sophisticated—and the simplest—hardware is useless. Here in Blue Bell, you might be called from your desk to join a team of data processing pioneers in a discussion of a new idea—maybe a revolutionary concept—because that's where we live. In tomorrow.

Want to talk it over? With people who like the computer business as much as you do? Then write. Your letter will be treated confidentially, and you'll get a prompt reply. The address: C. E. Cooke, Senior Employment Representative, UNIVAC Data Processing Division, Dept D111, Box 8100, Philadelphia, Pa. 19101.

Write today and make an appointment with tomorrow

UNIVAC
Data Processing Division

An equal opportunity employer M/F

cially in management information systems), we only require average values of some sort. Average values are ready made for a possible sampling application, since they are by their own nature statistical variates. However, any type of output data not audata is a sampling candidate before or during the run. This data not audata, we will call stochastic data for generality, which implies that a direct sampling possibility exists in the processing of its stodata (acronym). Sampling possibilities exist at the various levels of system development involving audata, but not to the same extent.

SAMPLING-DATA REDUCTION BY DATA SYSTEM STATUS:

Sampling, by no means has to be confined to internal program processing. Its basic purpose is to reduce a mass of data to a few simple numbers descriptive of the mass data set, which incidentally is a goal characteristic of management information systems. This broader concept of data and processing reduction is the one we wish to emphasize here. It extends from system design feasibility studies to audits of implemented systems. We will next describe some broad classes of systems design and processing status in which sampling may be useful.

- 1.0 Systems Design Feasibility: In systems design it sometimes occurs that the range of possible or likely input values of a parameter are unknown at the design feasibility stage. Quite often, it is possible to arrive at good estimates of this range by sampling existing files, and calculating confidence intervals on the sampling mean of the parameter. This for example, could be critical in deciding the field size requirements in information retrieval modules of any system.
- 2.0 Design for Input Data Reduction: If all of the required data outputs are Stodata, there is a good case for reducing the input data by sampling before it ever reaches the keypunching stage. This approach reduces all work but some initial programming. (See note on bottom of Table 1.)

- 3.0 Implementation Sampling: In some large systems, important questions remain after the basic system design and programming have been accomplished, as to the extent of the implementation problem. One approach to this problem is to implement the operational programs on a sampling basis i.e., over sections of the files to controlled, defined alpha range of input data et al. This approach to debugging eliminates the massive interference to existing files and procedures that results from the usual early debugging requirement of running dual operating systems simultaneously throughout the whole new system debugging cycle.
- 4.0 Normal Processing—Data Taping: During many business accounting type processing runs, additional data is desired for management information purposes in the form of averages per some set of categories. It may save substantial CPU time, to program an interrupt sampling scheme that would only process during the interrupt. The CPU trade-off is total marginal processing versus interrupt processing time. (Note: The possibilities inherent in multiprocessing mode of computer operation using this approach.)
- 4.1 Special (Data Tap) Processing of a Standard File: Management information systems may be able to tap existing tape or disk files to obtain data input where the required output is of the Stodata type, say a series of averages. Sampling then becomes a logical approach.
- 5.0 Normal Processing: During a normal run, it may be desirable to establish that the exact (audit trail) sequence of calculations is correct. Rather than force a series of dumps, some output (preferably a printer) could be programmed to print out the audit trail of the calculation in process, on a sampling interrupt basis. (The interrupt could be a sense switch type which would give the auditor a great satisfaction of flipping it himself and this could be done on a random time basis.)

TABLE I

SYSTEM STATUS	SAMPLING OBJECTIVE	GENERAL EXAMPLE	SAMPLING SCHEMES	PROGRAMMING REQUIREMENTS
1.0 Systems Design Feasibility (Before Systems Design)	Estimate input parameter ranges, (from either AUDATA or STODATA)	Establish if the standard A, B, C inventory categories are practical and estimate the size of each	Simple Random to Strata-Cluster	Generally none unless 4.0 or 4.1 involved
2.0 Design for Input Data Reduction (During Systems Design)	Reduce input Data for CPU savings, (STODATA output only)	Management Information e.g., changes in average service call time or costs	Same	None for Systematic sampling* others may require some. See Yates 60.
3.0 Implementation Sampling, (After Design, Before Implementation)	Sample System Implementation Problems (AUDATA or STODATA Systems)	On master tape merges, determine mismatch percentage/on disk-determine percentage overflow in Index Sequential Mode	Tapes generally Strata-Cluster/ Disks generally simple random	Little; either to merge register on tapes, or random number inquiry status
4.0 Normal Processing—Data Tapping	Sample Stream of AUDATA or STODATA (for Secondary STODATA use)	On a payroll run, type of the average income per professional category or department	Generally Simple Random	Amount Dependent upon sampling scheme employed
4.1 Special (Data Tap) Processing of a Standard File	Sample existing file (may be either AUDATA or STODATA)	On a standard billing file, extract, average bill per mailing zone	Simple Random to Strata-Cluster	Same**
5.0 Normal Processing	Establish proof of auditable process (AUDATA only)	Select on a sample basis, data Audit Trails to be followed for Auditors benefit	Simple Random	Simple or could even be done by time samples via sense switch

* A machine is available which sorts out every "n"th document or IBM card, in effect systematic sampling, Pitney-Bowes "Tickometer".

** Simple random time dumping of an existing tape file using one of the standard utility sense switch controlled tape dump routines, should be considered for one time only estimates, as in conjunction with 1.0 above.

TABULAR LIST OF APPLICATIONS BY SYSTEMS DESIGN STAGE:

The above list is meant to summarize the above arguments and serve as an interest stimulator in the possibilities that abound. I am certain it is capable of great expansion both by experience and good thinking. ■

BIBLIOGRAPHY

1. Cochran, W. G., Sampling Techniques, Wiley & Sons, N. Y. 63
2. Cyert, R. M. & Davidson, H. J., Statistical Sampling for Accounting Information, Prentice-Hall, N. J. 62
3. Eisenhart C., Deming L., and Martin C., Tables Describing Small-Sample Properties of the Mean, Median, Standard Deviation and Other Statistics Technical Note 191, National Bureau of Standards
4. Grant, E. L., Statistical Quality Control, McGraw-Hill, N. Y. 52
5. Hansen, Hurwitz, Madow, Sample Survey Methods and Theory, Vol. I and II, Wiley, N. Y. 53
6. Military Standard, Sampling Procedures and Tables for Inspection by Attributes, MIL-STD-105C, 18 July 1961
7. Moroney, M. J., Facts from Figures, Pelican Books, London 54
8. Tukey, John W., "The Future of Data Analysis", The Annals of Mathematical Statistics, Vol. 33, No. 1—March 1962
9. Yates, F., Sampling Methods for Censuses and Surveys, Griffin, London, 1960

PROGRAMMERS

DATA PROCESSING DESIGN SPECIALISTS

Many rewarding positions are immediately available with our rapidly expanding System Center near Hartford. These are truly ground-floor opportunities with a leader in the field.

DATA PROCESSING DESIGN SPECIALIST—Requires degree and 5 to 10 years of experience with on-line and real-time systems. Formulate system concepts, design and execute systems for information retrieval, communications switching, and graphics. Experience in quantitative comparative evaluation of alternative system designs and in preparation of technical proposals and report writing is desirable.


PROGRAMMERS—Requires degree and 3 to 5 years of experience with large, medium, or small scale computer information systems applications based on random access techniques. Emphasis on assembly language programming, use of real-time direct inquiry software, the creation and check out of operating systems and compilers and the production of automated graphics.


TO INTERVIEW, please forward your resume, stating present salary, to Mr. P. D. Blodgett, Personnel Dept., Hamilton Standard, Windsor Locks, Connecticut 06096.

An Equal Opportunity Employer

**Hamilton
Standard**

**U
A**
DIVISION OF UNITED AIRCRAFT CORPORATION





DOCUMENTATION

THE VALUABLE BURDEN

Ned Chapin, Ph.D.

Data Processing Consultant
InfoSci Inc.

Dr. Ned Chapin received his Doctor of Philosophy in Business and Economics with a minor in Industrial Engineering, 1959, from Illinois Institute of Technology. In 1949 he earned a Master of Business Administration from University of Chicago. Dr. Chapin has written two books on computers and dozens of articles in various publications. He has taught systems, data processing, computer programming, production control and other business and engineering subjects in college. At present he is a data processing consultant.

Cost and Value

■ In this age of software, good software writers typically hate to do documentation. The challenge and stimulation that makes programing fun is missing from doing program documentation. Most software types regard program documentation as a chore—a necessary one perhaps, but nonetheless a distasteful one. Program documentation is part of the burdensome overhead price a software writer pays to keep his boss happy and to meet installation requirements.

Besides being a burden to produce, most program documentation is a burden to read. The average job of documentation done at most installations is incomplete, inconsistent from program to program, and in a format that is difficult to decipher. Essential parts are usually in no set order or arrangement. The result is that the programmer must search through the program documentation materials in order to locate the information which he needs, if that information is present at all.

Any programmer or analyst who has done program maintenance work, or who has been assigned to revise a program that even he him-

self wrote a year or more before, can testify to the value of complete, accurate, and comprehensive program documentation. Well done, program documentation enables the programmer or analyst to grasp quickly the algorithms used in a program, to find the portions of the coding which implement the various portions of the algorithm, and to assess quickly the consequences of a change of input data or format, of the output data or format, or of the algorithm itself. Good program documentation enables the programmer or analyst to strike quickly to the heart of program maintenance work and accomplish it efficiently.

The absence of good program documentation leads a programmer or analyst to rethink the algorithm, to ferret out the details of the ways in which the input format and data affect the algorithm, and the operation of the program, and to sleuth relentlessly after the reasons why some unwanted data appear mysteriously in the output. Rethinking is hard work and very time consuming. The joy of original creation is rarely present. The organization gains no more from having a program corrected at a cost of many man hours of rethinking, than it does from having a program corrected quickly and efficiently through the assistance of good program documentation. The benefit to the organization is the same. But the cost to the organization can be drastically higher in the absence of good program documentation.

The advantages of program documentation are so well known that program documentation is given lip service in almost every computer installation. Rare indeed is the analyst, programmer, programming supervisor, operations director, manager of data processing, or manager of systems who decries documentation. Most sing its praises, and note its defects—or even occasionally its near absence—in their installations.

A few voices can be heard that program documentation is unneeded for COBOL, FORTRAN, PL/1, ALGOL, and the programs written in like languages. The language, some claim, is self-documenting, and hence no further documentation is needed. This is a very narrow view of what documentation comprises. To see the full picture, let us review briefly the objectives of program documentation, the advantages, the levels, and the elements of program documentation.

Objectives

Objective #1 of program documentation is to provide a written record of what the program directs the computer to do and how the computer is to do it. Since the program controls the computer's operation, information about what the program directs provides information about the way the computer performs its work, but not necessarily about what that work is.

Objective #2 of program documentation is to provide a written record of what the computer accepts as input and what it produces as output. This information tells what work the computer does in a way that reveals how this work contributes to and is a part of the over-all system. This information describes what the raw materials are that the computer uses, and what the products are that the computer produces from them.

Objective #3 of program documentation is to provide a means of communicating about a computer program from one human being to another. Specifically, program documentation is *not* concerned with providing information to or from a computer or other machinery about a program. Program documentation is designed for human consumption only.

Objective #4 of program documentation is to provide information towards four specific ends: documentation and program status, man-machine interface, data specifications, and program logic. Appropriately defined, these cover the major topics.

Thus, program and documentation status inform about when the program was revised, by whom it was written, of which system it is a part, and how fast it executes. Who authorized or made changes and when they were made is also part of the status information.

The man-machine interface description informs about human performance needed to make the computer and peripheral equipment operate correctly. This describes what a person

It's free. The new 1968 Edition.

Our National Computer Salary Survey and Opportunities Analysis.

This is it. The all-new 1968 edition of Source Edp's FREE 20-page Computer Salary Survey and Opportunities Analysis. It's a summary of computer salaries by 24 separate levels of professional and managerial experience ranging up to \$75,000. Plus a comprehensive analysis of current trends in computer employment.

All of this information has been compiled, analyzed and put together by some of the most knowledgeable people in the business. The people at Source Edp. Source Edp is the only placement firm staffed by computer professionals for computer professionals. It's their business to know the data processing field.

To get your free copy of the 1968 Edition of Source Edp's Computer Salary Survey and Opportunities Analysis just circle the reader inquiry card. To speed delivery write directly to:



Where computer professionals place computer professionals

Chicago—David B. Grimes, 100 S. Wacker Drive (312) 782-0857
 Detroit—Charles S. Walther, 2990 West Grand Blvd. (313) 871-5210
 Los Angeles—Robert C. Davis, 3470 Wilshire Blvd. (213) 386-5500
 Minneapolis—Fred L. Anderson, 507 Marquette (612) 332-8735
 New York—Edward R. Golden, 1414 Ave. of the Americas (212) 752-8260
 San Francisco—Richard O. Clark, 111 Pine Street (415) 434-2410

Client companies assume our charges.

For more information, circle No. 10 on the Reader Service Card

Important Programming Texts From McGraw-Hill

1. PROGRAMMING LANGUAGES, INFORMATION STRUCTURES, AND MACHINE ORGANIZATION

Peter Wegner, Cornell University. McGraw-Hill Series in Computer Science. 408 pages, \$10.95. The unique purpose of this book is to develop in depth a unified framework for the study of programming languages.

2. PROGRAMMING SYSTEMS AND LANGUAGES

Saul Rosen, State University of New York, Stonybrook. McGraw-Hill Series in Computer Science. 392 pages, \$12.50. A selection of previously published and unpublished reports containing descriptions of the most important programming languages and discussing many of the most important programming system concepts.

10 DAYS FREE EXAMINATION

McGraw-Hill Book Company

Box 402, Hightstown, New Jersey 08520

Send me the book(s) circled below for 10 days on approval. In 10 days I will remit for the book(s) I keep, plus a few cents for delivery costs, and return the unwanted book(s) postpaid. (We pay delivery costs if you remit with this coupon—same return privilege.) Include sales tax if applicable.

1. 689810 2. 537084

NAME (print) _____

STREET ADDRESS _____

CITY _____

STATE _____ ZIP _____

For prices and terms outside U.S., write McGraw-Hill Int'l., N.Y.C.

62SA58

For more information, circle No. 9 on the Reader Service Card



ATTENTION **EDP** EMPLOYERS!

She's a **JOB-HOPPER!**

... a very skilled Job-Hopper. And if you have a temporary peak work load in Electronic Data Processing, she's just the girl for you.

Our Job-Hopper service includes key punch operators, tab computer operators, computer programmers... plus EDP systems and management people.

Just phone. Our EDP "Job-Hoppers" are available right now.

ELECTRONIC SYSTEMS PERSONNEL AGENCY



Detroit: 1601 Fisher Building (313) 872-7855
Los Angeles: 3700 Wilshire Blvd. ... (213) 388-3205
Montreal: (opening soon)
Pittsburgh: 2204 Lawyers Building . (412) 391-6450
Seattle: 400 108th Street, N.E. (206) 455-1555
Toronto: 42 Charles Street, East ... (416) 929-3177

must do to enable adequate performance from the computer.

The data specification information pictures the data handled by the computer. The contents of records, the data formats, and the control data used are part of this information.

The program logic information delineates the way the program directs the computer to take the input data, transform it, and produce from it the output data.

Advantages and Documentation

Helps make a program belong to an organization. Programs are collections of symbols which in and of themselves typically have no obvious meaning. The meaning is known only to the creator of the symbols and not known to others in the organization. Program documentation restates these symbols which have private meanings to the programmers who created them, into symbols that have public meaning broadly throughout the organization. Without documentation a program is rather like a dog who obeys only one master. But programs are created by individuals for the benefit and use of their organizations.

Helps the programmer think clearly about program structure and choice of algorithm. When the programmer knows that what he specifies in his program will be presented for public view, he usually feels more compelled to search for and utilize clearly thought out and efficient algorithms for accomplishing the work of the program. A well reasoned, adequate, and comprehensive approach stands inspection better than something put together on a hit-or-miss basis. With program documentation the result typically is better programming, faster operating time, and fewer bugs.

Helps protect the organization against forgetting. When the programmer who wrote the program initially is assigned to other work, the forgetting process begins. Within a few months, the programmer typically has forgotten major significant details, and within years most of the details about a program he has written. Yet with program documentation, the organization has available all of the facts in full detail at all times.

Helps reduce the costs of personnel turnover. When a person who created the program resigns, falls ill, goes on vacation, takes a leave of absence, or is promoted or fired, knowledge about the program often leaves with him. Program documentation keeps that knowledge about the program in the organization, and thus helps protect the organization against the cost and time of redoing work.

Assists in training new programmers. When programmers are added to a staff or assigned to new work, program documentation provides information about other programs in use in the organization and about how programming is done in the organization. As such, it saves valuable

- ☐ Please change my address
☐ Please enter my subscription

SUBSCRIBER SERVICE

FOR CHANGE OF ADDRESS

ATTACH LABEL HERE

If you're moving please let us know 5 weeks before changing your address. If you do not have your label print your old address below.

Old home address _____

City, State _____ (Zip)

Mail to: Software Age, 1020 Church
St., Evanston, Ill. 60201

Please fill out the blanks below
whether you are changing your
address or requesting a new sub-
scription.

My Specialty _____

prime experience in what industry? _____

- ☐ Technical Degree
☐ Non-Technical Degree
☐ No Degree
☐ I have analog/hybrid exp.

_____ year born

Name _____

New home address _____

City, State _____


(Zip Code)

NEW


THREE DIMENSIONAL DRAWING INSTRUMENTS

FOR ACCURATE—DIMENSIONABLE—SCALEABLE—PICTORIAL—MECHANICAL DRAWING

ISOMETRIC



DIMETRIC



TRIMETRIC




ISOMETRIC DRAWING SET NO. 353

Set consists of:

- 1—Isometric Scale No. O-1
- 1—Isometric Roc-N-Edge No. O-2
- 1—35° Ellipse Protractor
- 1—Isometric Exploded View Assembly Sheet No. O-353-EVA
- 1—Instruction Sheet No. GS-368
- "Best of the Year" Award Announcement With Entry Form



THIS IS THE BASIC
GRAPHIC-STANDARD
ISOMETRIC CUBE




\$11.25
SET COMPLETE


DIMETRIC DRAWING SET NO. 424

Set consists of:

- 1—Dimetric Scale No. D-1
- 1—Dimetric Scale No. D-2
- 1—Dimetric Roc-N-Edge No. D-3
- 1—20° Ellipse Protractor
- 1—40° Ellipse Protractor
- 1—Dimetric Exploded View Assembly Sheet No. D-424-EVA
- 1—Instruction Sheet No. GS-368
- "Best of the Year" Award Announcement With Entry Form



THIS IS THE BASIC
GRAPHIC-STANDARD
DIMETRIC CUBE




\$16.50
SET COMPLETE

TRIMETRIC DRAWING SET NO. 525

Set consists of:

- 1—Trimetric Scale No. T-1
- 1—Trimetric Scale No. T-2
- 1—Trimetric Scale No. T-3
- 1—Trimetric Roc-N-Edge No. T-4
- 1—20° Ellipse Protractor
- 1—25° Ellipse Protractor
- 1—50° Ellipse Protractor
- 1—Trimetric Exploded View Assembly Sheet No. T-525-EVA
- 1—Trimetric Exploded View Assembly Sheet No. FT-525-EVA
- 1—Instruction Sheet No. GS-368
- "Best of the Year" Award Announcement With Entry Form



THESE ARE THE BASIC
GRAPHIC-STANDARD
TRIMETRIC CUBES



\$23.00
SET COMPLETE

TEN ELLIPSE PROTRACTORS SET NO. 101

LAMINATED SO THE
GRADUATIONS CAN
NEVER WEAR OFF



\$20.50
SET COMPLETE

SA-5

Send check with order to: **SCIENCE/SYSTEMS**, P. O. Box 1176, Evanston, Illinois 60204
Max, 1968

supervisory and training time in getting new programmers to be productive.

Assists in upgrading programmers. The senior programmers' "tricks of the trade," their techniques, and their successful approaches can be studied and copied by all programmers through the medium of program documentation. This permits each programmer to learn from all the others.

Assists in estimating the extensiveness of program changes. Program documentation lays out all the facts about each program that are relevant and significant points. It provides the basic data required for evaluating and making program changes. Each place in the program that needs to be changed and the way in which it needs to be changed to meet the new requirements can be more readily found with program documentation.

Helps decrease the cost of debugging. With all the facts about a program laid out before him, the programmer can more easily detect, diagnose, and correct errors in the program. This assumes that program documentation is begun prior to the time that program testing is begun. If this be so, then the programmer has been called upon to anticipate all the vital facts about the program. This very anticipation often catches mistakes.

Encourages the use of standard coding con-

ventions. For example, the programmer's assignment of names to data and to parts of the program are more likely to follow standard practice if the programmer's work is open to public inspection in the organization via program documentation. Standard approaches in methods of calling subroutines, handling of input and output errors, initializing input areas, and the like, are more likely to be followed when program documentation is done consistently.

Encourages standardization in the description of computer operations. This is made possible in part by the use of standard formats and standard terminology in the documentation itself. This, in turn, encourages programmers and analysts to think about problems in terms of standard building blocks, standard formats, and standard terminology in the organizations. This helps speed up and sharpen problem definition and tends to reduce programming time.

Aids in scheduling computer operation in an organization. How long a job will run, what factors affect the timing, and by how much, are more easily evaluated when program documentation exists in good form.

Partially documents the system. Since the system typically is built in major parts of computer operations, the documentation of the individual computer operations taken collectively constitutes a partial documentation of the system.

Levels of Documentation

Program documentation typically is useful in an organization at three levels: general overview, computer operations, and program and system maintenance. Each of these levels of documentation can be used by persons primarily concerned with other levels, as for example, a programmer may use data at several levels for different purposes.

At the overview level, persons who use program documentation typically seek a general understanding of what the computer does and how it does it, what it accepts as input, and what it produces as output. The overview level provides the broad picture.

At the operation level, those who use program documentation seek direction on how to set up the computer and peripheral equipment to make a run. They seek detailed information about the data and equipment to be used, and options available, and the operator intervention alternatives, for example.

At the maintenance level, those who use program documentation seek typically general and detailed information about what the program directs the computer to do, how it directs it to do this, and upon what specific items of data the operations are to be performed. Full and complete coverage of all details is needed in a well organized form.

Major Documentation Elements

Revision Status. This provides an introduction to the rest of the program documentation be-

PROGRAMMERS PROGRAMMER/ANALYSTS SYSTEMS ANALYSTS



**Professional
Career
Centers, Inc.**

*In this age of specialization let a specialist help
you make sure your next move is the correct move.*

For FREE SALARY ANALYSIS based upon the latest industry salary curves, send your resume to

PROFESSIONAL CAREER CENTERS, INC.

4641 Montgomery Avenue, Bethesda, Maryland 20014
(Suburban Washington, D. C.)

or call 301/657-2760

Nationwide and Overseas

ENGINEERS AND SCIENTISTS RESEARCH/DESIGN/DEVELOPMENT

BS, MA, PhD—Physics, MATH, EE, AE, IE, Ch, ChE
Career Opportunities available NOW with over 800 major
Client—Companies.

*Starting salaries from \$8000 to \$30,000
In confidence and under no obligation, call (collect) to
discuss interest or forward your resume to Joe Gregory.*



**70 STATE STREET
BOSTON, MASS. 02109
Richmond 2-5040**

ONE OF AMERICA'S FOREMOST EMPLOYMENT SERVICES

cause it provides information about the currency of the documentation and the position of the program in the system. As such, this element of program documentation provides information at the overview level about status.

System Charts. A system chart or system flow-chart preferably in U.S.A. Standard format provides graphically the basic information about the input and output for the program. As such, this element of program documentation provides information at the overview level about status, format, and logic.

Program Description. A description in words, preferably non-technical, about what the program does, what it uses as input, what it produces as output, and how it produces the output from the input, serves as a useful accompaniment to the system chart. The program description provides information on the overview level about format and logic.

Operation Sheet. The operation sheet supplies detailed information about how to set up the computer for runs of the program, what data are to be used as input, how to call the program, how to set up each item of peripheral equipment used, and how to label the output. This element of program documentation provides information at the operation level about the man-machine interface.

Halt List. The major options open to the console and peripheral equipment operators are sometimes identified by computer halts. The halt list enumerates these specifically giving the reasons for each and the action alternatives available. As such, this element of program documentation provides information at the operation level about the man-machine interface.

Card Formats. For the computers that do not utilize punched cards as a primary medium of input and do not utilize the punched cards for control input to the operating system, information on card formats is irrelevant. Most computers and most operating systems in use today use punched cards either for data input or for the control input. The card formats provide the detailed information about the cards needed and the fields on each. As such, this element of program documentation provides information at the operation level about format, logic, and the man-machine interface.

Input-Output Formats. Information about the data formats in storage at the time of input or output is typically shown in the input and output format. As such, this element of program documentation typically provides information at the maintenance level about format and logic. For greater usefulness, input-output formats normally show only those fields which are utilized or active in the program.

Algorithm. Any of several devices can be appropriately used for the task of stating in condensed form the algorithm utilized in the

program. In some circumstances, a mathematical symbolism may appear appropriate. In others, decision tables provide a convenient way of expressing the algorithm. Occasionally, other devices are useful. In any event, this element of program documentation provides information at the maintenance level about status and logic.

Summary Flow Diagram. The summary flow diagram or summary program flowchart serves as a directory or index to the detailed flow diagram. This diagram is most useful if it is prepared in U.S.A. Standard format, and uses the recommended notations. As such this element of program documentation provides information at the maintenance level about logic.

Detailed Flow Diagram. The level of detail in the detailed flow diagram or detailed program flowchart is normally determined by the level of detail in the coding of the program. Thus, the level of detail for a program written in a simple symbolic language is normally more detailed than is the level of detail for a program which was written in COBOL, FORTRAN, ALGOL, or PL/I. In either case, the diagram and the program list should cross-reference. The detailed flow diagram provides a graphic picture of the logic of the program. It is most useful is presented in U.S.A. Standard format using the recommended notations. As such, this element of program documentation provides information at the maintenance level about logic.

what's so good
about our

"TIME SHARING" SYSTEM?

we'll tell you!

When you're looking for a career challenge, you don't care to be a remote station. You want to come up with the right answer as quickly as the computer does when you feed it a problem. But you also wish to feel there is a human element involved.

That's where we come in. At MANAGEMENT SCIENTISTS we are on line at all times. As consultants to prestige firms here and abroad, we know WHERE the action is—WHERE your career future lies. And after evaluation of your background, we waste no time in directing you to the most rewarding job opportunities.

At present we are recruiting for talented professionals in

- TIME SHARING/REAL TIME
- SOFTWARE DEVELOPMENT
- OPERATIONS RESEARCH
- SYSTEMS DESIGN
- BUSINESS/SCIENTIFIC PROGRAMMING

For details, send us your resume, in confidence, including salary history and geographical preference.

**Management
Scientists, Inc.**

101 Park Ave.—Dept. SA 5-68
New York, N.Y. 10017
(212) 532-7710

Exclusively: DATA PROCESSING & MANAGEMENT SCIENCES
Career Planners—Recruitment Specialists

HAVE YOU HEARD OF

CASES

Let our 360 evaluate your qualifications against all orders in CASES (Computerized Applicant Search, Evaluation and Selection) for one year. Positions are located in all areas of the country.

Send us a resume along with your geographic restrictions and salary requirements and CASES will search for you.

If you don't have a resume send us your address and we will forward you a simplified INPUT form. No cost or obligation. All replies strictly confidential.

N. T. McNichols

FOX-MORRIS ASSOCIATES

1500 Chestnut Street
Philadelphia, Pennsylvania 19102

**Modern, progressive Chicago
based college needs—**

- ANALYST/PROGRAMMER
- SYSTEMS/PROCEDURES PLANNER
- COMPUTER OPERATOR

Computer applications being developed in financial and student accounting, statistical analysis and various areas of institutional research utilizing a system 360, model 30.

Send complete resume of experience and education including salary requirements, to:

Mr. Ken Ward at

NORTHEASTERN ILLINOIS STATE COLLEGE

Bryn Mawr at St. Louis Avenue Chicago, Illinois 60625

An Equal Opportunity Employer

PROGRAMMERS—ENGINEERS

Washington, D.C. • New York • New Jersey • New England • Philadelphia • Chicago • Minnesota • Texas • Ohio • Florida • Arizona • California • Southeast Asia

If you have a B.S., M.S. or Ph.D. and you are experienced or interested in any of the following, contact us immediately for free career counseling and an objective analysis of your position in today's market.

- | | | |
|-----------------------------|----------------------------|--------------------------|
| PROGRAMMERS | • Systems Simulation | • Digital Logic Design |
| • Management Info Systems | • Software Development | • Digital Circuit Design |
| • Information Retrieval | • Communications | • Digital Communications |
| • Command & Control | SYSTEMS ENGINEERS | • Systems Integration |
| • Aerospace Applications | • Reliability Analysis | • Soft Ware Analysis |
| • Real Time/On Line Systems | • Digital Computer Systems | • Oceanography |

Salaries range from \$8,200 to \$25,000. Our client companies assume all fees. Forward resume in confidence, or call (collect): Mr. Martin E. Sheridan (Area Code 703) 524-7660.

SHERIDAN ASSOCIATES INC.

1901 North Fort Myer Dr., Suite 1010, Arlington, Virginia 22209
(Just over the Potomac from Washington, D. C.)
Personnel Consultants to the Computer Industry

AVAILABLE NOW—PROGRAMMERS/ANALYSTS

- | | |
|--|------------|
| 1. B.S. Deg. 2 yrs. COBOL sys/360 MIS Programming | 9.3K |
| 2. B.S. Deg. 10 yrs. Sys/Prog. Supv. Fin., Hosp., Ins. | 13.2K |
| 3. BSEE 1 1/2 yrs. FORTRAN/MAP Programming | 9.0K |
| 4. B.S. Deg. 1 yr. FORTRAN Prog. 1620/CDC 8090 | 8.0K |
| 5. BS/MBA Supv. Sys/Prog. Mfg., Fin., Dist. | 14.5K |
| 6. B.S. Deg. Prog/Analyt. 6 yrs. exp. FORTRAN, etc. | 12.0K |
| 7. B.S. Deg. Prog/Analyt. M.I.S. COBOL 360/50-60, 6 yrs. | 12.0K |
| 8. B.S. Deg. Sys-EDP Sales. 3 yrs. | 12.0K base |

A NEW SERVICE FOR EDP PROFESSIONALS ONLY

We offer the competent professional an opportunity to evaluate his present position and to determine whether by associating with another company he will—challenge his interests—advance his career—increase his income. In complete confidence and without cost or obligation CALL OR WRITE



CARL PARKS
HARPER ASSOCIATES
EXECUTIVE RECRUITING AGENCY
3600 Wilshire Blvd., Los Angeles, Calif.
Phone (213) 386-7041

Sample Input-Output Forms. Sample input-output forms provide graphic examples to programmers, analysts, and operators about the appearance of correct input and output data. As such, this element of program documentation provides information at the operation and sometimes the maintenance levels about format and the man-machine interface.

Program Listing. The most useful program listings are those that show both the source and object language, and a symbol table cross-reference. This is because the maintenance work sometimes involves making object level language changes without recompiling in order to compensate for deficiencies in logic, or in compilation, or to handle situations not adequately provided for by the source language. Easy cross-reference to the diagram is also very helpful, as are comments in the coding. This element of documentation provides information at the maintenance level about the logic.

Conclusion

These twelve elements of program documentation imply a philosophy of computer operation. That philosophy is that the programmer tells the computer operator how the computer is to be operated, and not vice-versa. By contrast, in some documentation schemes, it is the task of the console operator to build the documentation by stating how he succeeded in getting the computer to run the job successfully. He is provided with forms on which he is asked to report how he set up the job, what he did at each halt, and what the results were.

The documentation approach presented here is particularly applicable to those installations using operating systems, or those in which the programmer and the operator are clearly separate persons. Under these conditions, the console operator can note on the console log sheet any unusual conditions that arose and can make a reference to the program documentation if needed. Thus, the console log sheet, rather than the program documentation, becomes the record of what the console operator did.

Under the approach presented here, program documentation is the task of the programmer. It is a burden on him at the time of programming and debugging, since he must create it to reflect a programmer's knowledge of and approach to programming. At its best, the approach goes back to the basic objectives of documentation. The record of what the program does and how it does it, and what the program accepts as input and what it produces as output must be complete enough and accurate enough to serve at the three levels noted. The intensiveness of use of these levels depends upon and varies from organization to organization. But, regardless of the intensiveness of use, program documentation is basically to communicate easily and intelligibly the important facts and relationships that distinguish a program.

TROUBLE-TRAN PRESENTS

XTRAN'S ADVENTURES IN FORTRAN

BY GEORGE N. VASSILAKIS/TRW

ART: A. DOUGHERTY/TRW

PROBLEM #3

```
C MAIN PROGRAM
  ALPHA = -90.
  BETA = 180
  10 A = SIGN (ALPHA, BETA)
  .
  .
  .
  END
```

```
FUNCTION SIGN (A,B)
  IF (A-B) 1, 2, 3
  1 SIGN = -1.
  RETURN
  2 SIGN = 0.
  RETURN
  3 SIGN = +1.
  RETURN
  END
```

WHAT DO YOU THINK
IS THE VALUE OF A
AFTER STATEMENT 10
IS EXECUTED?

HAVE YOU GOT
THE ANSWER?

BETTER
THINK
ABOUT IT
AGAIN!

TROUBLE-TRAN

for fun and profit

Send your ANSWER to the problems
posed here in each issue to:

TROUBLE-TRAN EDITOR

software age

1020 Church St., Evanston, Illinois 60201

You can also profit by submitting PROBLEMS
for this feature. If your problem in FORTRAN
programming is selected for use in this feature,
you will receive \$25.00

Contest Rules:

1. ASA standard FORTRAN IV is assumed.
2. The IBM 7094 FORTRAN IV compiler is used in verifying answers.

The correct answer bearing the earliest
postmark will net the reader submitting
it \$25.00

The second correct answer with
earliest postmark wins \$15.00

XTRAN'S ANSWER TO LAST MONTH'S PROBLEM

PROBLEM #2

THE PURPOSE OF THIS PROBLEM WAS TO EMPHASIZE THE FACT THAT "UPON EXITING FROM A DO BY SATISFYING THE DO, THE INDEX MUST BE REDEFINED BEFORE IT IS USED IN COMPUTATIONS." WHEN WE WRITE: DO 100 I=1,10 THE INDEX VARIABLE I IS INITIALIZED WITH 1, AND THE 2's COMPLEMENT OF 1 IS PLACED IN AN INDEX REGISTER. LOOPING IS CONTROLLED BY THE INDEX REGISTER AND NOT THE INDEX VARIABLE I.

NOW LET US LOOK AT THE PROBLEM ONCE MORE.

```
DIMENSION X(100), Y(100)
100 FORMAT (4E15.5)
K=1
DO 20 J=1, 50
  KK=K+1
  READ (2, 100) (X(I), Y(1), I=K, KK)
  20 K=I+1
```

THE READ STATEMENT INCLUDES AN IMPLIED DO, WHICH IS EQUIVALENT TO A DO STATEMENT. SINCE LOOPING IS CONTROLLED BY THE CORRESPONDING INDEX REGISTER AND NOT BY THE INDEX VARIABLE, THE VALUE OF I AFTER EACH READ IS EQUAL TO K AND NOT KK.

LOOKING INTO ARRAY X, WE SEE THAT ON THE FIRST READ WE READ INTO LOCATIONS X(1), X(2). ON THE SECOND READ WE READ INTO LOCATIONS X(2) AND X(3). AS YOU SEE, EVERY SECOND PAIR OF DATA IS LOST, WITH THE EXCEPTION OF THE LAST ONE. TO CORRECT CHANGE: 20 K=K+2

TEST NO.		G	FUNCTION																																				LBL	UPDATE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	

The source language coding is used for generating the RCA Universal Test Equipment Compiler (UTEC) language program.

SOFTWARE MANAGEMENT

(Continued from page 14)

overlooked in the design process. These must then be "patched" into the program, often at decreased program execution efficiency in order to minimize the interaction on the completed sections of the program. By reducing each sub-program task to a separate, though subordinate specification, all requirements may be defined in detail at the outset.

Task subdivisions in hardware design tasks usually fall into neatly defined physical unit boundaries. This is seldom the case in software efforts. Software can be broken down only into a small number of separate programs. One may be for system pre-acceptance testing, another for operational control and a third for maintenance. Beyond such major divisions, there is little natural subdivision. When no definitive specifications are imposed on the task coordinate, the problem is often handled by assigning a major task to a task force of several programmers, all of which have overlapping responsibility. In such circumstances the more ambitious member of the team (not necessarily the task coordinator or even the most capable programmer) must bear the brunt of the task. By substituting indigenous leadership for documented directives a good deal of inefficiency often results. Some work, incompatible with the final approach, is necessarily scrapped while other parts are reworked. Specification control provides an explicit means for subtask definition, ensuring compatibility by facing the problem at

the outset rather than when well along the design path.

Without a detailed work statement and subordinate specifications, attempting to ascertain percentage of completion of a software task is generally a guessing game. This problem arises from the lack of visual evidence of accomplishment in partially completed programs. Generally there is far more paper work observable part way down the road to completion than when the program is finished. This is due to the overlapping coverage of subtask programmers, extensive rework and alternate coding generated to cover alternative approaches. All of which point to a lack of definitive direction in the detailed design stage. In hardware tasks, pieces fit together more naturally. Hence, the end of one phase and start of another is more definite, thereby leading to a simpler, more accurate assessment of percentage of completion. If software were generated in conformance to a network of subordinate specifications, fulfillment of such specifications would provide an accurate measure of accomplishment.

Finished product performance is judged against an overall requirement specification and is thus fairly easily ascertained. At that level, software performance can be determined just as readily as hardware performance if not more so. While it is true that some software bugs may exist for years before detection, these are minor deviations to desired performance. Once debugged and operational, programs simply do not fail; so once properly demonstrated, they perform without error forever.

The need for de-personalization of tasks in scientific and engineering endeavors is self-evident. Programming should also be approached just as objectively as hardware designs

After August 15th write direct to advertiser

RUSH DETAILS ON ITEMS REFERENCED BY CIRCLED NUMBERS

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40
41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60
61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80

Name ----- Title -----

Company ----- Address -----

City ----- State ----- Zip -----

JOB FUNCTION

A. Systems Analyst	G. EDP Instructor
B. Math/Math Analyst	H. EDP Consultant
C. Operations Research	J. EDP Operator
D. Scientific Programmer	K. EDP Student
E. Business Programmer	L. Other
F. EDP Management	

TYPE OF INDUSTRY

M. Aerospace/Defense Industry
N. Other Industry
O. Commerce/Finance
P. Transportation/Utilities
Q. Research Organization
R. Govt./Military
S. EDP Consulting
T. Education/Library
U. Other

NO. OF EMPL.
IN E-D-P DEPT.

1. Under 10
2. 10-25
3. 26-50
4. 51-100
5. Over 100

FIRST CLASS
PERMIT NO. 217
CLINTON, IOWA

B U S I N E S S R E P L Y M A I L

NO POSTAGE STAMP NECESSARY IF MAILED IN THE UNITED STATES

POSTAGE WILL BE PAID BY

software age

P. O. BOX 2680

CLINTON, IOWA 52732



and specifications provide objectivity, if nothing more.

Standardization in hardware is a recognized necessity for many reasons, not the least of which is the interplay of subunits. Software tasks involving many individuals have similar problems of interplay. The fact that this interplay is less evident makes it more of a problem. Standardization would go a long way toward facilitating this interplay. Specifications, with their use of applicable document references, provide a convenient means of imposing basic standards on the overall requirements of a peculiar task.

Any design well controlled by documentation provides a sound basis for related development efforts to come. To appreciate the design considerations of a program, a good deal more than a finished program is required. With specifications covering each facet of software development, later projects can see exactly the logic, objectives and accomplishments of a past software effort.

In any effort, a manager's span of control is effectively increased by relegating definable direction to written procedures and reserving his personal attention to problem areas as they develop. Most of the software details are directly related to the ultimate task requirement and thus may be documented at the start of a project. Specifications provide such a vehicle of documented control.

Specifications, as definitive documents, provide historical information on past projects. This was discussed as it pertains to follow-on work. Specifications also provide a tool for orientation and training of personnel. This is an equally valuable tool for software as it is in hardware development.

The final consideration for specification control deals with design changes. This has been deferred to last not because it is least in importance but because it is perhaps most worthy of consideration and comment. Nothing can be more detrimental to schedules, costs and even the success of a task than uncontrolled changes. This has been recognized in hardware design efforts. Formal and often elaborate systems for design changes exist at every phase of system design. It becomes increasingly difficult and expensive to make changes the further along the process a product has progressed. Yet, no matter how undesirable, changes are inevitable. They must be contended with but they cannot be allowed to get out of control. Hence, in software, as in hardware designs, only mandatory changes should be permitted and budgets must be realigned periodically to adjust to work load effects of approved changes.

Somehow widespread miscomprehension exists as to the effects of changes on software efforts. Because programs are essentially "paper designs" there is a tendency to feel that nothing is firm. Perhaps it is simpler to change a few coded



Time-Sharing

*is today's
foremost opportunity.*

General Electric

wants you to make
the most of it!

CAREERS IN:

- PROGRAMMING/SYSTEMS DESIGN
- CUSTOMER APPLICATIONS
- SALES

The time-sharing industry is growing today at the rate of 75 per cent per year. *General Electric Time-Sharing is growing even faster!*

In more than 40 metropolitan areas across the country, GE Time-Sharing is already a fact. And this is only the beginning. You can still get in on the ground floor and take advantage of the unparalleled career opportunity represented by our current openings for:

SOFTWARE SYSTEMS DESIGNERS/PROGRAMMERS

BS in engineering, mathematics, or physics and at least 2 years in scientific software design. Positions are in suburban Washington, D.C.

CUSTOMER APPLICATIONS SPECIALISTS

Minimum of 2 years in FORTRAN, machine or assembly language on large-scale computers; degree preferred. Positions available nationwide.

SALES REPRESENTATIVES

Should have a degree and 2 or more years of sales (preferably technical), programming, or related experience. Positions available nationwide.

Get the Facts...Call Us Collect

For the full story about GE Time-Sharing careers, please call Mr. J. J. Guisti collect at (301) OL 4-9360, or send your resume to J. J. Guisti at: General Electric Co., Information Service Dept., Room 302, 7735 Old Georgetown Road, Bethesda, Maryland 20014. If you write, be sure to include your home telephone number.

INFORMATION SERVICE DEPARTMENT

GENERAL  ELECTRIC

An equal opportunity employer M&F

A typical sheet from a computer listing of a test program has been prepared for the Land Combat Support System. Source language (left side of sheet) is that of the RCA Universal Test Equipment Compiler and object language (right side of sheet) is machine language for the RCA Land Combat Support System (LCSS).

In summary, this paper has attempted to show the similarity between hardware and software

REFERENCES

- (1) B. L. Ryle, "An Engineering Approach to Configuration Management", Proceedings of the 1966 Automatic Support System Symposium, St. Louis, Missouri, Section of IEEE.
- (2) Project SETE, N.Y.U., "Problems and Pitfalls in Automatic Test Computer Programming", May 1965.
- (3) Bellcomm, Inc., "Management Procedures In Computer Programming for Apollo", Interim Report for NASA, TR-64-222-1, 30 November 1964.

Did you notice something wrong with the printout, "Summarized Transaction Analysis Report" on page 21 of March SOFTWARE AGE? John Paul Nicholson did. And he is in 2nd Grade, Queen of Heaven School, Albuquerque, New Mexico.

Thank You
John Paul Nicholson
2nd Grades
Queen of Heaven School
Albuquerque, New Mex.

P.S. My dad helped me write this letter.



These tiny metal rods are the heart of a new computer memory. The rods, only a tenth of an inch long, replace conventional magnetic cores. They literally "dance" into centers of minute solenoids when placed in a pulsating magnetic field.

SOFTWARE of the CENTURY

William P. Keating

Director of Basic Software
The National Cash Register Co.

■ The family idea dominated the software development program of the Century Series of Computers.

User growth and usage patterns dictated the sensibility of a plan for complete upward compatibility of both hardware and software through an entire family of systems.

Three goals were set:

1. The total system marketed must be customer oriented. It must be designed to solve the real world, functional problems of prospective user organizations. Customers must be able to install and program the Century Series with a minimum of effort and expense.
2. The entire effort must be on time. The hardware and software must both be available to the initial user of the Century Series.
3. Modularity, to the highest degree

possible, was mandatory for both hardware and software.

To accomplish these objectives, NCR started with a study designed specifically to isolate and define the functional requirements which would be placed on software by a user's object program at the time of execution. Once we were sure that we were providing those requirements necessary to simplify the programming burden, attention then turned to optimizing the space, time, and cost variables associated with including these functions within our system. Our design considerations point out several categories of software, each having their own implementation requirements. These categories are:

1. General software facilities, which are program dependent, con-

tinuously required and frequently called upon. Involved here are such facilities as data and file referencing. To meet this need, a series of variably generated sub-routines was incorporated in the system software. These generator routines determine what type of peripheral, file device, and internal logic is required, and the necessary commands are generated to fulfill the program at execution time. Such tailoring allows considerable savings both in memory and running time requirements of user systems, when compared with fixed sub-routine or large executive designs.

2. General facilities, which must be available at all times, which are used frequently, but are not program dependent. The executive includes capabilities such as interrupt handling, simultaneity control for all

peripherals, and software overlay calling routines.

3. General capabilities required throughout the running of the program but used only occasionally, such as peripheral unit initiations, file closing routines, error procedures, and logging. Communication to this logic is handled by the resident executive mentioned before. The executive will select and read into memory these infrequently used sub-routines, which provide full operating control of peripherals.

This concept of using supplementary disc storage provides the vital link in assuring upward compatibility between the smallest and largest members of the Century Series.

4. General procedures, which are required before and after a program run, to assure successful initiation, completion, and work flow. This is satisfied within the new software package by a job scheduling monitor system. This controls all program to program flow. It is re-



New NCR Century Series computers are based on design advances in ultra-high-speed thin-film memories, monolithic integrated circuitry and automated production techniques.

To a young Programmer-Analyst with something to say . . .

We're listening.

Our new, expanding EDP department is not only "open" to new ideas, but actively looking for them. Right now we're in the process of advancing our full scope management information system, utilizing a newly installed multi 360 third generation complex.

If you have 2-4 years commercial experience (some exposure to 7070 autocoder would be helpful) and an accounting, math or business administration degree (or equivalent) the opportunity to be heard, and contribute to a new development effort is sizeable.

We are a leading worldwide pharmaceutical company offering the ambitious programmer/analyst a true business opportunity inductive to creativity and individual recognition.

Tell us about yourself, and your salary requirements in a confidential resume. We'll listen.

Salaried Employment Representative

PARKE, DAVIS & COMPANY

Joseph Campau at the River
Detroit, Michigan 48232

An Equal Opportunity Employer

PARKE-DAVIS

sponsible for program loading and system setup. The sequence of programs to be performed can be maintained on disc and a high degree of selection flexibility controlled by dates or data is possible within the system.

The guaranteed use of the disc on all family members also allows the creation of a daily magnetic log for all operations, and performs other necessary housekeeping functions.

This log records the names of all user programs which have been run, all errors detected, and all system malfunctions. Among other things, it serves as an invaluable diagnostic tool for maintenance personnel.

The composite of the above features represent an advanced approach to operational problems. These capabilities help measurably in achieving the basic goal of making the Century Series easier for customers to use and operate.

After providing for the execution of the object user program, the next phase in the new software philosophy called for basic needs of user program compilation and testing. This cycle was broken into three segments:

1. Functions to be performed prior to compilation.
2. Actual compilation.
3. Post-compilation requirements.

These requirements are language independent in that they must be accounted for no matter what programming language is used. The Century system programmer will be provided a series of software routines and compilers to satisfy the requirements cited above.

Now...

DIGICOMP II - the "second generation" of the famous DigiComp,


enormously more "sophisticated" as additional "switches" and "core positions" permit many more decisions and "branching" possibilities.



Like its predecessor the DigiComp-I (see below) it is entirely mechanical in operation but affords the functions common to electronic computers in a form far more comprehensible. The best way ever to learn (or to teach) the principles of modern data processing.

\$16.95 Postpaid

DIGICOMP-I COMPUTER



Ingenious mechanical equivalent of an electronic digital computer. Can be "programmed" to perform, individually, every operation of a digital computer. Best thing ever for teaching binary math, how a computer operates, how and why problems must be broken down for machine solution. In kit form—1 hr. to assemble. **\$5.98 Postpaid**

WFF 'N PROOF

Developed in the course of the ALL Project (Accelerated Learning of Logic) Wff'nProof incorporates 21 games of progressive difficulty; has been used to teach propositional calculus to elementary school children but challenges the intellect of professional logicians. Complete with 224-page manual which is an introduction to the world of modern logic; filled with valuable tips to clear thinking.

\$6.25 Postpaid



OH WAH REE

The ancient game of mathematical strategy which has intrigued millions for more than 30 centuries. A game at once so simple in its basics that a pre-schooler can enjoy it yet so complex in its possibilities that its fascination multiplies with the mathematical grasp of the player.


\$7.95 Postpaid



CONFIGURATIONS

Based on concepts from the geometry of incidence, CONFIGURATIONS is a series of intriguing mathematical and geometric puzzles that will challenge and delight those who enjoy careful reasoning. It is authored by Professor Harold L. Dowart, Chairman of the Mathematics Department, Trinity College, Hartford.

\$4.95 Postpaid



TWIXT

Another famous "bookshelf" game, package matches that of Oh-Wah-Ree. A stimulating game with a fascinating chess-like strategy of move and countermove. Two or four players.

\$7.95 Postpaid

SCIENCE/SYSTEMS

P. O. Box 1176
Evanston, Ill. 60204

SA-5

Please send me at the address below:

.....
.....
.....
.....

Save \$1 by ordering any 3 items or \$2
on any order for 4 or more of the above
(Games are shipped from separate warehouses)

(name)

(address)

(city)

(state)

(zip code)

Illinois residents add 5% OES

New!

PORTABLE DRAFTING MACHINE

for

- ★ HOME
- ★ OFFICE
- ★ PLANT
- ★ FIELD
- ★ TRAVEL



No longer need you struggle with loose T-square, triangles, protractor and scales when you want to make precise sketches in-plant, in-flight, in the field or at home. The DRAFTETTE® gives you the familiar convenience of your office board in compact, portable form. The #9-B provides interchangeable 6 x 9" scale, 360° protractor reading in 5° increments. Scale calibrated in 16ths or in 50ths and millimeters (specify scale desired in ordering). May be purchased ready-mounted on 16 x 21" light-weight board or unmounted to attach to your own board or to a pad of paper. When not in use, can be folded like a jack-knife to fit into desk or brief-case.

#9-B—Including Board \$18.00
#9—Same without Board 15.00
Extra Scales 4.50
Carrying Case for #9-B .. 2.25

SCIENCE/SYSTEMS

P. O. Box 1176, Evanston, Ill. 60204

Prior to compilation, all programs must be put into proper form, format, and sequence for processing. The new NCR software handles these requirements with a package known as SPUR (Source Program Utility Routines). These routines handle all of the sequencing and correction of source programs. Maintenance of source program libraries and the ability to include commonly used routines or data definitions from other programs substantially reduce the raw input requirements of the programming. This program handles all Century languages.

The language and subsequent compiler selection of the Century Series began with a definitive study aimed at classifying the types of users we were most likely to encounter. This evaluation took into account that a whole new family of computers was involved and that the prospective users would range for the neophyte up through the experienced sophisticates. Based on these initially established requirements, the NCR software group elected to provide the following programming languages to users of the new computer systems.

For scientific programmers, two versions of FORTRAN are available. This approach makes scientific programming feasible at every level of the Century Series. For minimal systems (16K memory, 2 disc packs) FORTRAN II is provided. On larger systems, FORTRAN IV serves as the scientific language.

Recognizing and providing for the needs of business programmers who require a standardized language created the need for a COBOL Compiler. Different levels of COBOL are offered with the Century Series. A basic level provides a compiler usable on the minimum 16K configuration. Customers installing medium and larger systems have COBOL Compilers which are scaled to the capabilities of their equipment and conform to the latest USASI draft standards.

An additional effort has been made to meet the requirements of both the neophyte who wishes to program utilizing higher-level, easier to use, generator and macro techniques or the highly sophisticated user or software writer who needs an assembly level language which makes it possible for him to code programs

in one-for-one correspondence with machine functions. In supporting the Century family, we have met these requirements. Specifically, through the development of a single, multi-level language, NEAT/3. NEAT/3 provides a vocabulary ranging from instructions similar to basic COBOL on up to powerful reoccurring data processing functions.

As the basis for development of this segment of the NEAT/3 Compiler, an analysis was made of large numbers of actual user programs to classify the functional tasks required of informational system compilers. These, it was found, fall into two broad categories:

1. Basic tasks. Typical is ADD A to B.
2. Tasks incorporating many parameters and wide scope. This type of command corresponds in capability to Report Writing. NEAT/3 includes nine separate functions of this degree of complexity in its initial version. Furthermore, the vocabulary is open ended, providing for continuing and expansion. Examples of functions available include file updating, report writing, and several others. You have seen in the slides shown earlier the type of questionnaire the programmer answers in requesting these tasks.

Although necessarily brief, it is hoped that the description of the compilers offered with the Century Series will answer the needs of the already initiated scientific and business users with the COBOL and FORTRAN Compilers and also provides a direct appeal to prospective users looking for an easy and/or fast way to write programs through the use of NEAT/3.

To fulfill their responsibility to users, the programming language facilities provided with the Century offer the capacity to debug, as well as to code, symbolically. This symbolic debugging capability is offered with both NEAT/3 and COBOL.

Furthermore, to be of real value, it is felt that the option of symbolic debugging should be available to the programmer at any time. Under the new NCR programming language concept, for example, the programmer is not restricted to stipulating his chosen debugging tech-

In conclusion, it is hoped that this article summarizes the philosophical element and implementation approaches which have gone into the creation of system software for the Century Series. We must stress the ease and simplicity of working with the software philosophy enunciated here is fully expandable to provide for any operating requirements of modern computer applications. User programs written for the smallest Century can run on any other system in the family. The universality and availability of the NCR software package surpasses the goals established at the beginning of the development. Without question, this combination of hardware and software provides a system unequaled in the industry today. ■

SA-5

new products

Atlantic Software Inc., a firm which specializes in marketing computer software, announces the **Data I** program. Data I is a special-purpose System 360/Spectra 70 utility designed to reduce file maintenance programming costs, and to eliminate one-time programs for data and file manipulation.

Data I is said to update tape or disk files from cards, tapes or disks in any format. It can also generate tape, disk or card files. Output formats are completely variable. Program requires 64K core, will operate under DOS and OS with any combination of disk and tape I/O.

Experience with Data I already totals several man/years, with programming time savings running as high as 95%, according to Atlantic Software.

For more information circle No. 80
on the Reader Service Card

• • •

A proprietary software package, **ALTRAN**, has been recently introduced by Applications Software Inc., San Pedro, California. ALTRAN (Assembly Language TRANslator), translates SDS 900 Series SYMBOL or META-SYMBOL source language programs to SDS Sigma 5/7 META-SYMBOL. ALTRAN runs on either SDS Sigma 5/7 or SDS 9-Series computers. This latter operational characteristic is especially significant, since it enables a user to begin program conversion long before the new machine is installed.

ALTRAN is said to yield 90% translation to SDS Sigma META-SYMBOL. A translated program is more than twice as fast as the old program. This is in contrast to simulated programs, which seriously degrade the performance of the SDS Sigma 5/7 computer, since the simulated programs are much slower than the original programs executed on SDS 900 Series computers. ALTRAN provides a user with many input/output options through the availability of in excess of 16 translation parameters.

For more information, circle No. 79
on the Reader Service Card

• • •

A program documentation binder made of Wilson Jones "Super-Flex" has been added to its line of EDP equipment specifically for use by programmers.

The Program Documentation Binder (Stock No. 03-1411) is one-piece construction, suited for systems in which the source documents, parameter cards and the program printout are of such size that they can be housed in a single unit. It is designed for maximum compactness and convenience. The printout side can be

loaded from top or bottom of the sheet body. The document side includes a vinyl envelope for the program's control cards and an index with printed insertable EDP titles. Available in 6 colors for coding programs.

For more information, circle No. 78
on the Reader Service Card

• • •

New electronic thermometer and switchbox by Atkins Technical Incorporated, monitors up to 20 points, displaying temperatures on 4½" taut-band meter and providing 0-50 mv signal to optional recorder. The thermistor probe switchbox can be programmed for dwell time on each point of 10 seconds to 5 minutes, and for sweep through 3, 7, 12, or the full 20 probes. The temperature indicator and the switchbox can be packaged together in a single cowling for portability as one device, or separately as shown.

For more information, circle No. 77
on the Reader Service Card

• • •

Potter Instrument Company has introduced a new, low-cost, single-capstan digital magnetic tape transport system for use with small and medium scale computers.

The new transport system—Model SC-1030, provides bidirectional tape speeds to 37.5 ips at 800 bpi, NRZI, as well as 1600 bpi phase modulated recording. The unit is fully 7- or 9-channel (IBM 729, 7330 and 360/2401, or ASCII) compatible.

Single-capstan design is used to drive the tape. A precision edge guidance system provides reliable tape control. Tape



EMPLOYMENT AGENCY
FOR
COMPUTER
PROFESSIONALS

Serving

- PHILADELPHIA
- NEW JERSEY
- NEW YORK

METROPOLITAN AREA

Experienced Programmers and Analysts from these areas may call collect anytime (24-hour answering service)

(609) 662-6621

OR SEND RESUME TO

HOWARD LEVIN

Director

RSVP SERVICES

304 Victor Avenue

Cherry Hill, N. J. 08034

RECRUITMENT • SELECTION • VOCATIONAL TRAINING
PLACEMENT FOR COMPUTER ORIENTED COMPANIES



EDP-SYSTEMS

WE SPECIALIZE IN CAREER CORRECTION

ARE YOU "UNDERED"?

UNDER . . . PAID or UNDER THE WRONG BOSS . . . UNDER THE
WRONG CLIMATE or UNDER PROMOTED

UNDER UTILIZED or UNDER THE WRONG HOURS . . . UNDER THE
WRONG POLICIES . . . or just "UNDERED"?

FOR "OVERING" . . . CALL WA 3-2640

LAWRENCE PERSONNEL

1015 Chestnut, Philadelphia, Pennsylvania 19107

FEE PAID BY CLIENT COMPANIES • NO CONTRACTS • ALWAYS CONFIDENTIAL

loading is semi-automatic in less than 15 seconds. In operation, the oxide side of the tape touches no stationary surface except the read/write head and tape cleaner, greatly increasing tape life and data reliability.

Other specifications: Rewind: Less than 4 minutes (2400 foot reel). Start time: 8ms; Start distance: $0.165 \pm .025$ "; Stop time: 7ms; Stop distance: $0.110 \pm .020$ "; Speed tolerance: $\pm 5\%$; Dynamic skew: 5 usec.

For more information, circle No. 76 on the Reader Service Card

• • •

A new high-speed information retrieval software system has been announced by Computer Corporation of America. Called the Model 101, the system is designed for use with IBM System/360 hardware using disk packs as the data storage medium.

The Model 101 has the capability of storing large as well as small files—over 100,000 individual records may be accommodated. Information may be retrieved simultaneously from several independent files through the systems cross-referencing capability.

Data input and output is handled by COBOL-compatible magnetic tape. Alternately, input and output may be handled through punched cards and high speed line printer.

Hardware requirements for operation of the Model 101 information retrieval system include: IBM System/360, Model 30 or larger with 65K bytes of core storage (minimum); 1 to 4 Model 2311 disk drives for data storage; DOS operating system; three magnetic tape drives, line printer, and card reader.

For more information, circle No. 75 on the Reader Service Card

• • •

EPSCO, Incorporated, has introduced the DATRAC IV, a high-speed analog-to-digital converter plug-in-module for data processing applications.

DATRAC IV's conversion speed of one microsecond per bit allows up to 100,000 conversions per second. At top speed, the


unit's overall accuracy is .05 per cent (plus-or-minus one-half the least significant bit).

Special features of the DATRAC IV include exclusive use of DTL integrated circuits for the input buffer amplifier, comparator, reference supply and all logic functions. Precision attenuator networks and switches are in discrete form.

Operating characteristics of the DATRAC IV include 10 or 11 binary bit resolution, parallel output data for micro-logic interfacing, negative 2's complement code and a 100,000 cycle word rate (KHz).

For more information, circle No. 74 on the Reader Service Card

• • •



Dawn Products Co. is offering a new product to hold computer reels. With this Reel Caddy one can carry from 6 to 12 reels at a time. The Reel Caddies are of heavy gauge wire, nickel plated with rubber feet to protect table or desk top.

For more information, circle No. 73 on the Reader Service Card

• • •

PACFAC—a disk pack analysis and control program for the IBM/360—was announced by Software Resources Corporation. PACFAC interrogates the volume table of contents of any IBM disk pack to

LIVE IN DENVER!

Experienced Programmers and Analysts for Engineering and Commercial Applications on IBM S/360 using OS PL/I and FORTRAN

Join a small, select group of dedicated professionals working on a wide variety of applications in the engineering-construction field. You'll like the locality, the company and the future. Send resume in confidence to D. P. Weisbrod.

Stearns-Roger
CORPORATION

P.O. Box 5888, Denver, Colo. 80217
An equal opportunity employer

EDP

- Programmers
- Analysts
- D. P. Management

Fast, Efficient, confidential service to individuals seeking new positions in the field of data processing. Call, write or visit one of our offices. Data Processing Placement since 1959.

CLIENT
COMPANIES
ASSUME
OUR FEE

**Computer Personnel
Agency, Inc.**

KENT MURPHY
12 Geary Street, San Francisco, Calif.
Phone: 982-0840

NATIONWIDE DATA PROCESSING
OPPORTUNITIES

INFORMATION PROCESSING JOURNAL

A QUARTERLY REFERENCE JOURNAL DEVOTED TO THE
THEORY, DESIGN, AND APPLICATION OF ELECTRONIC COMPUTERS

DESIGNED TO ASSIST THE COMPUTER SPECIALIST LOCATE INFORMATION
On a Specific Subject or Topic, in a Fraction of the Time required by Conventional Literature Search.

PRESENTED IN ABSTRACT FORM, COMPLETELY INDEXED
By Subject, Topic, Source and Author and Thoroughly Cross-referenced.

6,000 ABSTRACTS PER YEAR

CAMBRIDGE COMMUNICATIONS CORPORATION

1612 K St. N.W.
Washington, D.C. 20006
(202) 393-1239

Specialists in Scientific Information Retrieval for over 10 years

For more information, circle No. 11 on the Reader Service Card

SCIENTIFIC PROGRAMMERS

If you have a degree in mathematics, physics, or a related science and at least one year of scientific programming, using Fortran, you will find gratifying work involvement at the Computer Division of EMR.

Our Programmers are involved in developing "State-Of-The-Art" Programs which are used to reduce sophisticated information. Your work involvement will be in the development of operating systems for real-time or time-shared applications contributing directly to new generation Software design.

Your inquiry concerning these professional positions is invited.

Please call

PETER J. SCHROTH (612) 888-0155



8001 Bloomington Freeway
Bloomington, Minnesota 55420



PROGRAMMERS SYSTEMS ANALYSTS

Nationwide

With the installation and implementation of our unique National Marketing Analysis System (NMAS), Input, Inc. is now able to bring the nation's complex and ever-changing computer community into remarkable focus. Through the mass of exclusive information available to us through NMAS and by employing an innovative "search and solve" technique, our staff of trained consultants can lock in on the myriad complexities of your specific career requirements with an accuracy unparalleled in the field.

Fields covered include digital hardware design, systems analysis and programming of software, management information systems, and a variety of sophisticated scientific and commercial applications. We welcome your inquiries. Contact Mr. Lincoln Bouve or Mr. William Caine at 202/298-7510 for additional information or submit resume in confidence. Client companies assume all fees.

input, inc.

815 connecticut avenue, n. w.
washington, d. c. 20006
e.o.e./mf suite 1200

determine what files are present, their activity status, their organization, size and location as well as the size and location of available free space. It also provides a permanent history of inoperative tracks.

PACFAC permits complete machine analysis of file space in place of laborious manual methods. By providing improved documentation and control of file storage, PACFAC can reduce disk pack inventory costs in many installations.

PACFAC output lists all files alphabetically and lists unused space sequentially by cylinder and track. It can also sequentially list an entire disk pack or data cell, both files and free space.

For more information, circle No. 72
on the Reader Service Card

The GECENT III Postprocessor System, a software support program written for General Electric Mark Century numerical control systems used in conjunction with the APT III computer system, is now available to users of Mark Century NC systems.

Taking advantage of the flexible overlay capabilities in third generation computers, and by varying the number of overlays, the new GECENT III Postprocessor can be made to fit large and small computers, multiple programming computers, or eventually a time-sharing computer. Initial tests of the new program indicate computer processing times of GECENT III to be from 1/6th to 1/12th as long as the GECENT II program which it replaces.

The structure of GECENT III is based upon the ability to sectionalize those sub-routines which apply to a particular type of machine tool (i.e. positioning, lathe, mill, etc.).

For more information, circle No. 71
on the Reader Service Card

The Scanbe Model 600 vertical equipment drawer has been designed to provide modular storage for any desired number of card file units.

The Model 600 provides complete access to circuit cards, connectors and wiring during assembly and later servicing; allows extra space between front and rear panels and the large card storage section;

features a built-in flexibility of the card files, card-mounting sets and vertical drawer system that allows portions of the drawer to be reserved for power supplies or auxiliary units; and includes frame dimensions which can be modified to fit any desired depth of file.

For more information, circle No. 70
on the Reader Service Card



Data processing managers can gain time-saving ideas from the new 16-page data processing labels, tags and specialties catalog just issued by the Allen Hollander Co., Inc.

The line, consisting of many stock and custom imprinted variations, offers a wide range of sizes, shapes, substances and adhesives that make it possible to retrieve information from data processing media, print it out at high speed and then use it for such functions as addressing, identifying, numbering, recording, posting, pricing, grading, coding, inventory, mailing, reporting and accounting.

For more information, circle No. 69
on the Reader Service Card

Now available from Keltec Industries, a Division of Aiken Industries, Inc., is the Model CP-2811 Data Conversion System, a compact unit (5 1/4 x 19 x 21 1/2 inches)

☐ Please change my address ☐ Please enter my subscription

ATTACH LABEL HERE FOR CHANGE OF ADDRESS

If you're moving please let us know 5 weeks before changing your address. If you do not have your label print your old address below.

Old home address _____

City, State _____ (Zip)

Name _____

New home address _____

City, State _____ (Zip code)

☐ Technical Degree
☐ Non-Technical Degree
☐ No Degree

year born _____
exp. analog/hybrid

prime experience in what industry?

My Specialty _____

Please fill out the blanks below whether you are changing your address or requesting a new subscription.

Mail to: Software Age, 1020 Church St., Evanston, Ill. 60201

SUBSCRIBER SERVICE

which accepts analog information from up to 20 different sources and generates digital data in IBM format at minimum cost and with maximum simplicity. Design features include a 20-channel solid-state scanner (multiplexer), a 12-bit analog-to-digital converter, and a scan rate of 2000 channels per second. Outputs and controls are compatible with Digi-Data Incremental Tape Recorders and most other magnetic and punched-paper-tape recorders.

For more information, circle No. 68
on the Reader Service Card

• • •

A proprietary software package introduced by California Computer Products, Inc. eliminates the need for special software in the conversion of CRT images to plotted hard copies.

Designed for use with the IBM 2250 display unit and any CalComp plotter, the new program automatically converts a 2250 CRT image, or selected portion, into the correct format for plotter reproduction, either on-line or off-line.

For more information, circle No. 67
on the Reader Service Card

• • •



A new, sub-miniature digital readout elapsed time indicator has been developed by the Industrial Timing Division of Sessions, Forestville, Connecticut.

The compact unit, which reads out in tenths to 10,000, is available immediately in a 120-volt, 60-cycle package with a variety of mountings available to meet customer specifications. The device may be equipped at an optional cost with a device that will enable the meter to be reset. The maintenance timer incorporates

$\frac{1}{8}$ " high characters in easy-to-read bold-face figures. Standard leads are stripped and induction soldered; length and color per customer specifications.

The digital ETI supplies exact computations.

For more information, circle No. 66
on the Reader Service Card

• • •



Computer Lab workbook presents a wide array of logic gates, gate combinations, flip-flops, etc. for student use in learning how a computer works—from a single gate operation, to wiring and controlling the operation of subsystems. Computer Lab is manufactured by Digital Equipment Corporation, and uses integrated circuits similar to those found in the company's latest computers.

For more information, circle No. 65
on the Reader Service Card

• • •

Featuring a double safe construction with an outer safe and an inner repository, the new data-bank fire vault by Wright Line, a division of Barry Wright Corporation, is designed to provide maximum protection for vital EDP records stored on either tape or disk packs.

The new vault carries the Underwriters Laboratories, 150° two hour label for storage of EDP media. It will hold interior temperature and humidity well below the 150° F. 85% R.H. limit at which read out errors and losses can occur even when the vault is exposed to a raging fire of up to two hours duration.

For more information, circle No. 64
on the Reader Service Card

• • •

PROGRAM YOUR CAREER FOR SUCCESS
EXPLORE NATIONWIDE EMPLOYMENT OPPORTUNITIES THRU ONE CONTACT

PROGRAMMERS D P MANAGERS ANALYSTS

STARTING SALARIES \$8,000 TO \$20,000 (ALL FEE PAID)
SEND YOUR FLOW CHART (RESUME) OR CALL (212) MU 3-6000

ROBERT BOOK, EDP/SYSTEMS MGR

KNORR ASSOCIATES INC

52 VANDERBILT AVE NEW YORK CITY 10017
THE PROFESSIONAL AGENCY SERVING THE EDP COMMUNITY

EDP PLACEMENT SERVICE

The Callahan Center is a placement organization which specializes exclusively in EDP personnel. We offer the following:

1. Fee paid positions.
2. Night and Saturday interviews.
3. Resume dictation service.
4. 24 hour intensive search.
5. No contract to sign.
6. Strict confidence.
7. A weekly review of your resume for one year if necessary.
8. Each individual receives the personal attention of Mr. Callahan.

CALLAHAN CENTER FOR COMPUTER PERSONNEL

Suite 414 Boulevard Building
1819 J. F. K. Boulevard, Phila., Pa. 19103

CALL COLLECT: (215) 567-4811

PROGRAMMERS MANAGEMENT INFORMATION SYSTEMS

JOIN THE BETTER IDEA PEOPLE AT PHILCO-FORD

Design specialists to develop management information systems. Must have a 4-5 years experience with high level program language such as COBOL and FORTRAN IV. Must be familiar with large scale disc oriented computers. BS required. MS desirable.

call Don Rossier, Dept. 706-37
at 326-4350, ext. 4125
or send resume to

PHILCO-FORD CORPORATION

Space and Re-entry
Systems Division

An Equal Opportunity Employer

3870 Fabian Way, Bldg. 58L
Palo Alto, Calif. 94303

You don't change a company the scope of Montgomery Ward with timid measures. You do it with a totally unique programming effort geared to serve a total management information system from 8 different areas simultaneously!

You do it with a battery of IBM 360/50's, 40's, 30's. With hardware that comprises one of the largest commercial 3rd generation installations in the nation!

Most of all, you do it with peo-

ple. Young, restless, skilled people... including programmers and systems analysts with COBOL or BAL experience who recognize the potential in helping re-structure an entire system.

If you're a person who wants to get things done, there's no better place to turn your energies loose than right here. At the changing Montgomery Ward. Contact: M. K. Fenwick, Personnel Representative, Corporate Systems Division.

What's a merchandiser like Montgomery Ward doing with a computer complex like this?



MONTGOMERY WARD

6th Floor, Data Center/140 S. State Street, Chicago, Illinois 60603
An Equal Opportunity Employer

Digitronics Corporation has extended its line of paper tape equipment to cover low-speed, asynchronous reading and punching applications. The company's new **low-speed reader**, Model 2060, reads any EIA standard 11/16 (5 channel) to 1-inch (8 channel) punched tape and operates at speeds to 60 characters per second. A simple drive, utilizing solenoids which do not require lubrication, is used to move tape. For high reliability, bifurcated contacts are employed to perform the read function.

The new Model 1560 **Paper Tape Punch** operates asynchronously at rates to 60 characters per second and records data in five through eight-level code. Featuring in-line loading of tape, solenoids which require no lubrication and optional tape supply reel and take-up winder, the Model 1560 is available in four packages styles to meet most packaging requirements.

For more information, circle No. 62
on the Reader Service Card

• • •

A new full color brochure describing Rol-a-chart **visual control boards** features a full-scale sample chart section and a guide to visual control, according to the Wm. A. Steward Company.

To assist the planner, the sample chart section is large enough to actually layout a scheduling system. Typical examples are given showing a visual control system charted with marking pencils and the same visual control charted with magnets.

For more information, circle No. 61
on the Reader Service Card

• • •

Mathematical Engineering Associates, Inc. of Dallas has released **MANAGE**, a program which enables a computer installation to maintain its source programs on tapes or disks.

MANAGE is written in COBOL, and can be used on any tape computer which has COBOL capability. **MANAGE** maintains programs written in FORTRAN, COBOL, AUTOCODER, ALC and other machine languages.

Using **MANAGE**, a computer installation enters and carries its source language programs on a program master tape or disk. The installation's programmers then use their computer to add to, delete from, and otherwise maintain or resequence their programs. The master tape or disk in the **MANAGE** system is also used for computer input as well as to list any program or its modifications.

A **MANAGE** produced program listing is a program log that becomes part of program documentation. This **MANAGE** produced log shows exact modifications in each update run. The **MANAGE** log enables a programmer or manager to know exactly what statements have been altered in, added to, or deleted from a program, and the date and sequence of each such action.

For more information, circle No. 60
on the Reader Service Card

• • •

software age

THIS INQUIRY IS IN
DIRECT RESPONSE TO
YOUR ADVERTISEMENT
IN
SOFTWARE AGE
MAGAZINE

CONFIDENTIAL INQUIRY

Your original copy of this form will be retained at the offices of SOFTWARE AGE and will be used for no other purpose than to notify the specific firms which you have checked (on the reverse side) of your interest.

TYPE OR PRINT CLEARLY FOR PHOTO REPRODUCTION

JOB DESIRED: _____

List computer hardware knowledge (names of systems, tape, disk, terminals, etc.): _____

Programming specialties and years of experience (commercial, scientific, theoretical, experimental, analog, etc.): _____

Systems programming on which you have had development experience (compilers, assemblers, executives, monitors, O.S., etc. Indicate for what computer): _____

Programming languages used and extent of experience (COBOL, FORTRAN, etc.): _____

Applications programmed (aerospace, banking, insurance, math subroutines, compilers, etc.): _____

Systems analysis experience (card design, flow charting, operation analysis, etc.): _____

EDP management experience (include years and number of people reporting to you): _____

SALARY: _____ (current) _____ (desired) DATE OF AVAILABILITY: _____

EDUCATION: Indicate major as well as degree unless self-explanatory.

Degrees	Years	Schools
_____	_____	_____
_____	_____	_____
_____	_____	_____

EMPLOYMENT: Indicate present employment and previous jobs below.

Employer	City	Years	Title or Function	Name	Age
_____	_____	_____ to _____	_____ to _____	_____	_____
_____	_____	_____ to _____	_____ to _____	_____	_____
_____	_____	_____ to _____	_____ to _____	_____	_____

Home Address _____ Home Phone _____

(city) (state) (ZIP code) U.S. Citizen? _____

Security Clearance _____ Location Preference _____

Marital Status _____

BE SURE YOU HAVE CHECKED ON REVERSE SIDE
THE COMPANIES YOU WANT TO SEE THIS INQUIRY.
PUT FORM IN STAMPED ENVELOPE AND MAIL TO:

software age

MAGAZINE

1020 CHURCH ST., EVANSTON, ILL. 60201

check your interests here

Fill in the confidential inquiry form on the other side of this sheet. (Be sure to use this form. We cannot process multi-page resumes; and this form provides all the information advertisers require to screen applicants. If further information is desired,

you will hear from the advertiser direct.) Then, circle below the numbers of those companies to which you want copies of your form sent. Mail to SOFTWARE AGE, 1020 Church Street, Evanston, Illinois 60201.

CIRCLE BELOW:	Page
1. AC Electronics Div. of GMC	2nd Cover
2. Allis-Chalmers	20
3. The Boeing Co., Commercial Div.	5
4. California Blue Shield	4th Cover
5. EMR, Computer Div.	42
6. General Electric Co., Information Service Dept.	33
7. Hamilton Standard Div. of UAC	23
8. Honeywell, Inc., Electronic Data Processing	3
9. IBM Corp.	7
10. ITT Federal Electric Corp.	19
11. Kimberly-Clark Corp.	9
12. LTV Aerospace Corp.	4
13. MIT Instrumentation Laboratory	11
14. Montgomery Ward Data Center	44
15. National Cash Register Co.	3rd Cover
16. North American Rockwell, Rocketdyne Div.	14
17. Northeastern Illinois State College	30
18. Parke, Davis & Co.	36
19. Philco-Ford Corp.	43
20. RCA Information Systems Div.	13
21. Sikorsky Aircraft	17
22. Stearns-Roger Corp.	41
23. Univac Data Processing Div.	22

CIRCLE BELOW:	Page
24. Univac Federal Systems Div.	18
25. Xerox Corp.	15

EMPLOYMENT AND SEARCH AGENCIES

26. Callahan Center for Computer Personnel	43
27. Computer Personnel Agency, Inc.	41
28. Electronic Systems Personnel Agency	26
29. Fox-Morris Associates	30
30. Harper Associates	30
31. Input, Inc.	42
32. Knorr Associates, Inc.	43
33. Lawrence Personnel	40
34. Management Scientists, Inc.	29
35. Nation-Wide Employment Agencies	28
36. Professional Career Centers	28
37. RSVP Services	40
38. Sheridan Associates	30
39. Source EDP	25

PRODUCTS AND SERVICES

Cambridge Communications Corp.	41
Data-Link Corp.	6
McGraw-Hill Book Co.	25
Science/Systems	10, 20, 27 & 37

☐ I do not now receive S/A. Please enter my FREE subscription.

.....
My Specialty

.....
Prime Experience in What Industry

☐ Technical Degree ☐ Non-Technical Degree ☐ No Degree

.....
Year Born ☐ I Have Analog/Hybrid Experience

software age

1020 Church Street
Evanston, Ill., 60201

**If you want a career with the only
big computer company that makes
retail data systems complete
from sales registers to computers,
where would you go?**

Guess again.


It's NCR, and this is not the only surprise you may get if you take a closer look at NCR.

We're a company alive with new ideas, research, development. A year never passes without NCR increasing its investment in research. We have hundreds of engineers, chemists, and physicists exploring their own ideas for the company that's willing to wait and let them do it.


Take a closer look and you'll see that NCR makes computers, electronic accounting systems, highly sophisticated solid-state communications systems for space and defense applications, and you'll see that even our good old cash registers have become advanced information machines for businessmen.

In a list of "emerging ideas of 1966," Business Management magazine credits NCR with two out of seven: pioneering in laser technology for recording data, and development of our new PCMI microform system that puts the Bible on a projector slide.

When you start looking, look closely at NCR. NCR can surprise you; maybe you have some surprises for us. Write to T. F. Wade, Executive and Professional Placement, NCR, Dayton, Ohio 45409.



An Equal Opportunity Employer. ®



CHALLENGE!

To the data processing professional, whose abilities are equal to the rapid growth and expanding opportunities of the largest prepaid medical health organization in the state of California, California Blue Shield.

We offer excellent salaries, working conditions conducive to creativity, superior benefits and an administrative policy designed to recognize capability. Our salary structure is reviewed regularly.

California Blue Shield is located in the Financial District of downtown San Francisco. Excellent world famous restaurants are in the immediate vicinity. The Bay Area is unexcelled for scenic beauty, recreational opportunities and cultural advantages.

A complete and detailed resume to Gene J. Gilbert, Manager of Employment, 720 California Street, San Francisco, California will be answered at once.

Aggressive/Creative EDP Systems

5-10 Years Experience. Highly experienced results-oriented systems talent with solid supervisory exposure and possessing the aggressiveness, human relation skills and maturity necessary to deal with all levels of company management.

Lead and Senior Programmer Talent

Highly experienced individuals with a minimum of 4 to 7 years experience. Knowledge of magnetic tape-oriented computer systems, random access and COBOL is necessary. Must possess advanced programming techniques and be familiar with implementation of computer systems. Supervisory and project responsibilities required on some positions.

All positions require self-starters with technical discipline, individuals who are imaginative, result and people oriented, have the ability to communicate, strong procedures experience (total system), and the ability to overcome obstacles.

We are an equal opportunity employer.



CALIFORNIA
BLUE SHIELD

CALIFORNIA PHYSICIANS' SERVICE